

# Armed Services Technical Information Agency

Because of our limited supply, you are requested to return this copy WHEN IT HAS SERVED YOUR PURPOSE so that it may be made available to other requesters. Your cooperation will be appreciated.

AD

29596

NOTICE: NO GOVERNMENT OR OTHER DRAWING, SPECIFICATION OR OTHER DATA ARE TO BE USED FOR ANY PURPOSE OTHER THAN IN CONNECTION WITH A DIRECTLY RELATED GOVERNMENT PROJECT WITHOUT THE WRITTEN PERMISSION OF THE U. S. GOVERNMENT THEREBY IMPOSING NO LIABILITY, AND NO OBLIGATION WHATSOEVER, AND THE FACT THAT THE GOVERNMENT HAS FORMULATED, PROMULGATED, OR IN ANY WAY SUPPLIED THE SAID DRAWING, SPECIFICATION, OR OTHER DATA IS NOT TO BE RELIED UPON BY INDIVIDUAL OR OTHERS AS AN IN ANY MANNER ENDORSING THE DESIGN OR ANY OTHER DESIGN OR CORPORATION, OR CONVEYING ANY FORM OF ENDORSEMENT TO MANUFACTURE, USE OR SALE. ANY PATENTED INVENTION THAT MAY IN ANY WAY BE RELATED THERETO.

Reproduced by

DOCUMENT SERVICE CENTER

KNOTT BUILDING, DAYTON, 2, OHIO

UNCLASSIFIED

AD NO 29596

ASTIA FILE COPY

ADC TECHNICAL REPORT 54-19

2 1

**SEMITRAILER MOUNTED OXYGEN OR NITROGEN  
GENERATING AND CHARGING PLANT**

**Part. 1. Design Study**

**H. V. FARROW**

**AIR PRODUCTS, INCORPORATED**

**JANUARY 1964**

**WRIGHT AIR DEVELOPMENT CENTER**

50

**BEST AVAILABLE COPY**

#### NOTICES

When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data, is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

The information furnished herewith is made available for study upon the understanding that the Government's proprietary interests in and relating thereto shall not be impaired. It is desired that the Judge Advocate (WJ), Wright Air Development Center, Wright-Patterson Air Force Base, Ohio, be promptly notified of any apparent conflict between the Government's proprietary interests and those of others.

WADC TECHNICAL REPORT 54-19  
Part 1

**SEMITRAILER MOUNTED OXYGEN OR NITROGEN  
GENERATING AND CHARGING PLANT**

**Part 1. Design Study**

*H. W. Farrow*

*Air Products, Incorporated*

*January 1954*

*Equipment Laboratory  
Contract No. AF 33(600)-19855  
RDO No. 660-128*

**Wright Air Development Center  
Air Research and Development Command  
United States Air Force  
Wright-Patterson Air Force Base, Ohio**

## FOREWORD

This report was prepared by Air Products, Incorporated, Allentown, Pennsylvania, on contract No. AF 33(600)-19855, dated 9 June 1952; Supplement Agreement No. 1, dated 2 March 1953; and Revision 1, dated 15 May 1953. Work was administered under the direction of C. R. Anderson, Vice-President-in-Charge-of-Engineering and H. W. Farrow acted as project engineer. The contract was initiated under Research and Development Order No. 660-128, "Improvement and Development of Oxygen Generating Plants and Auxiliary Equipment," by the Equipment Laboratory, Directorate of Laboratories, Wright Air Development Center, with A. M. Paulson serving as project engineer.

This is one of a series of three reports to be issued on this project. The second report will be issued upon completion of the operating tests on the mobile, liquid oxygen generator, while the third report will be issued upon completion of the entire program.

Included among those who cooperated in the study were C. J. Schilling, L. L. Volland, P. G. Foust, J. V. Fetterman of Air Products, Incorporated.


#### ABSTRACT

Design of a mobile generator capable of producing two tons per day of high-purity liquid oxygen or liquid nitrogen and capable of compressing the entire production capacity to 4000 PSIG as described. Flows of the operating cycle are pictured and discussed. Material and heat balances are calculated on the basis of theory and past experience gained from the fabrication of more than 500 oxygen generators, both mobile and stationary, of high- and low-purity type. Tentative specifications for the equipment components are listed.

#### PUBLICATION REVIEW

The publication of this report does not constitute approval by the Air Force of the findings or the conclusions contained therein. It is published only for the exchange and stimulation of ideas.

FOR THE COMMANDER:



RICHARD STOLLE  
Colonel, USAF  
Chief, Equipment Laboratory

### SUMMARY

To obtain the desired production of two tons per day of 99.5% pure liquid oxygen, or two tons per day of 99.0% pure liquid nitrogen, an air feed of approximately 1000 standard cubic feet per minute shall be used. This shall indicate a liquid oxygen recovery by weight of 4.29% or a liquid nitrogen recovery by weight of 3.7%. To operate the unit three diesel engines shall supply approximately 330 horsepower, which shall result in a ratio of approximately 1.1 pounds of liquid oxygen produced per pound of diesel fuel burned. A temperature approach of approximately 8°F shall be expected at the air inlet end of the heat exchanger. The estimated heat infiltration from ambient surroundings into the air separator shall be 1.5 B.T.U. per pound of air feed. It is estimated that the loss of air from the heat exchanger during the reversals, which occur every 10 minutes, shall be 3% of the total input. The semitrailer shall be approximately 32'-0" long, 9'-6" wide and 12'-0" high. These dimensions, which are reduced to a minimum, shall be for the greater part, dictated by the availability of equipment components in the air source section.

## CONTENTS

	<u>Page</u>
FOREWORD	ii
ABSTRACT	iii
SUMMARY	iv
SECTION I     CYCLE OF AIR SEPARATION	1
Figure 1    Liquid Nitrogen Cycle	2
Figure 2    Liquid Oxygen Cycle	3
Figure 3    Gaseous Nitrogen Cycle	4
Figure 4    Gaseous Oxygen Cycle	5
SECTION II    ELECTRIC POWER AND CONTROL	9
Figure 5    Wiring Diagram	10
SECTION III   THERMODYNAMIC CALCULATIONS	11
Figure 6    Liquid N <sub>2</sub> Heat Balance	11
Figure 7    Liquid Vapor Equilibrium Curve	18
Figure 8    Liquid O <sub>2</sub> Heat Balance	32
Figure 9    Gaseous Nitrogen Heat Balance	35
Figure 10   Gaseous Oxygen Heat Balance	38
SECTION IV    EQUIPMENT SPECIFICATIONS	41
Figure 11   Generator General Arrangement	42
SECTION V     GENERATOR MASTER VALVE AND TEMPERATURE INDEX	64

## SECTION I

### CYCLE OF AIR SEPARATION

#### General

The cycles of air separation for this generator are pictured on four Air Products, Incorporated Drawings numbered 42559, 42560, 42561 and 42562. Each will illustrate a phase of operation and will herein be referred to as Figures 1, 2, 3 and 4. The liquid product is produced by the distillation of liquid air into pure oxygen or nitrogen dependent on requirements. Atmospheric air which forms the raw material is filtered, compressed, freed of water vapor and carbon dioxide in reversing heat exchangers, and then liquefied by a combination of cooling and expansion. The pure product which results from the distillation of the liquid air is drawn off as a liquid at column operating pressure or, is fed as a liquid into special pumps which compress the product to any pressure up to 4000 PSIA. The cold high-pressure liquid product leaving the pump is warmed in a heat exchanger, and flows as a gas into cylinders or into some other receiver. Since this product is the result of distillation of liquid air, it can be considered absolutely dry for all conditions of use.


It is necessary to remove the water vapor and carbon dioxide contents from the air inasmuch as these impurities, if not removed, would, in a relatively short period of time, "freeze out" at the sub-zero temperatures involved and thus plug lines and render the generator inoperative.

#### Detailed Description

Atmospheric air is drawn through mechanical filters to remove any foreign matter which may be injurious to the equipment, and is then fed to an oil-free air compressor where its pressure is elevated to 100 PSIG. The air compressor is a three-stage unit, each stage consisting of a rotary blower which is direct-driven by a diesel engine through a suitable transmission. Some moisture, and also the heat of compression, are removed from the air in air-cooled inter- and aftercoolers.

The "high-pressure" air is then fed to the heat exchanger through a switch valve. This valve switches or reverses, at preset ten minute intervals, the heat exchanger passes for the incoming, high-pressure air and the effluent, low-pressure, waste air such that, the passes which were high-pressure air passes for the previous ten minutes then become effluent, waste air passes for the next ten minutes, and vice-versa. The remaining moistures, and also the carbon dioxide, in the high-pressure air are deposited in the heat exchanger at the different temperature levels which are in equilibrium with the vapor pressures and concentrations of the moisture and carbon dioxide. These deposits are made in the two passes alternately. While a deposit is being made in one pass, the deposit in the other pass is being "cleaned up" through the absorptive capacity of the dry, low-pressure, effluent, waste air.







# LEGEND

- VALVE OPEN
- VALVE CLOSED
- EXPANSION VALVE
- CHECK VALVE
- SAFETY POP VALVE
- CONTROLLER
- PRESSURE GAUGE
- FILTER
- LIQUID LEVEL GAUGE
- THERMOMETER
- TEMPERATURE INDICATOR
- THERMOCOUPLE
- ANALOG POINT

## AIR PRODUCTS, INCORPORATED

DESIGNED BY: J. J. JONES  
 DRAWN BY: J. J. JONES  
 CHECKED BY: J. J. JONES  
 APPROVED BY: J. J. JONES






**LEGEND**

VALVE OPEN  
 VALVE CLOSED  
 EXPANSION VALVE  
 CHECK VALVE  
 SAFETY POP VALVE  
 ORIFICE  
 PRESSURE GAUGE  
 FILTER  
 LIQUID LEVEL GAUGE  
 THERMOMETER  
 TEMPERATURE INDICATION  
 THERMODYNAMIC  
 ANALYSIS POINT


**AIR PRODUCTS, INCORPORATED**  
 EMMAUS, PENNSYLVANIA, U. S. A.

FIGURE 2 FLOW SHEET  
 LIQUID OXYGEN PRODUCTION  
 250 TON PER DAY  
 AIR FLOW GENERATOR

SCALE  
 DRAWN BY: APM  
 CHECKED BY: APM  
 APPROVED BY: APM




W40C TA 54-19 CT 1



AIR PRODUCTS, INCORPORATED  
 3901 UNIVERSITY AVENUE, U.S.A.

DATE: 1/1/68  
 DRAWN BY: [Signature]  
 CHECKED BY: [Signature]  
 SCALE: 1" = 10'-0"





VALVE OPEN  
 VALVE CLOSED  
 EXPANSION VALVE  
 CHECK VALVE  
 SAFETY VALVE  
 ORifice  
 PRESSURE GAUGE  
 FLOW  
 ZEROING LEVEL GAUGE  
 TEMPERATURE  
 TEMPERATURE INDICATOR  
 FLOW INDICATOR  
 ANALYSIS POINT

AIR PRODUCTS, INCORPORATED			
SHEET 1 OF 2			
GASOLINE OXYGEN PRODUCTION			
270 OXYGEN NITROGEN			
MOBILE GENERATOR			
DESIGNED BY	WCM	DATE	4/28/52
CHECKED BY	WCM	DATE	4/28/52
APPROVED BY	WCM	DATE	4/28/52

After leaving the heat exchanger, the high-pressure air, which is then a saturated vapor, enters the air liquefier. The liquefier is an extension of the heat exchanger surface, and in it, liquefaction of a portion of the incoming air is effected. This portion is the amount of liquefaction necessary to keep the cycle operating, and it is equivalent to, (1) the amount of liquid withdrawn as the final product plus, (2) the amount of liquid which is vaporized as a result of the influx of heat into the generator from the ambient surroundings plus, (3) the amount of liquid which is lost as a result of the expansion from high-pressure-air pressure to column operating pressure, the pressure at which the liquid product is withdrawn.

The partially liquefied, high-pressure air then enters the phase separator, where its liquid and vapor phases are divided and directed into different streams.

The liquid stream is expanded to approximately 6 PSIG after which it is passed through a silica gel type hydrocarbon adsorber. In the adsorber, removal of the hydrocarbon content is accomplished to prevent their accumulation to dangerous concentrations in the distillation column. After every 150 or more hours of operation, the adsorber is reactivated by means of an electrically heated stream of hot dry air which absorbs the hydrocarbons and carries them off to atmosphere. This air is tapped from the air supply to the turbo expander.

After the adsorber the liquid stream is fed to the sub-cooling jackets of the liquid product pumps to prevent vaporization of the pure liquid product when the pump is operating, and thus keep the pump efficiency high. The stream is then directed to the low pressure section of either the nitrogen or oxygen column depending on the final product required.

The vapor phase is further divided into two streams. One of these, representing 75% of the total air feed, passes through the cold section of the heat exchanger from the cold end to the warmer end, and then feeds the turbo expander. The exhaust from the expander joins the effluent waste air stream which leaves the column and enters the air liquefier.

In the case of producing oxygen the other vapor stream from the phase separator is expanded through a valve from high-pressure-air pressure to high-pressure column pressure, which is approximately 89 PSIA. This vapor enters the high-pressure column and is fed directly into the condenser where all of it is condensed by the product liquid oxygen which surrounds the tubes on the low-pressure-column side of the condenser. The resulting liquid is expanded to low-pressure-column pressure and introduced into the low-pressure column at the top as reflux. In order to prevent rare, inert gases such as neon, etc., which are found in the air, and which are not capable of being condensed by the liquid oxygen, from blanketing the condenser tube surfaces and thus impair their efficiencies, a stream is drawn off from the dome of the condenser and expanded into the effluent waste air stream which leaves the column. This non-condensable offtake, although very effective in accomplishing its purpose, is so very small in magnitude that it does not enter into the calculations for the material and heat balances.

The low-pressure column contains a number of bubble-cap pans of conventional design, which are fed at the proper points by the expanded liquid from the

incoming high-pressure air, and the expanded liquid from the high-pressure column. The liquid descending on these pans comes into intimate contact with the ascending vapors resulting from the column feeds as well as the vapors from the boiling oxygen which surrounds the tubes of the condenser. This intimate contact of vapor and liquid on each pan results in a gradual vaporization of the more-volatile constituent, nitrogen, and a condensation of the less-volatile constituent, oxygen. Sufficient pans are included in the low-pressure column to ensure that the liquid withdrawn from the bottom is 99.5% pure oxygen. Because the boiling point of argon is closer to the boiling point of oxygen than it is to the boiling point of nitrogen, it appears in the column in the vicinity of the oxygen, and shows up as the 0.5% impurity in the product oxygen.

Since there is only one product, oxygen, withdrawn from the column, the remaining oxygen and argon and all of the nitrogen leave the column at the top as a saturated vapor. This vapor passes through the oxygen subcooler where it subcools the product oxygen to prevent or reduce "flash" losses resulting from later expansion. After passing through the subcooler, it combines with the turbo expander exhaust and enters the air liquefier where it liquefies a portion of the incoming high-pressure air. From the air liquefier it passes through the heat exchanger where it both cools the incoming air to saturation temperature, and absorbs the moisture and carbon dioxide which were deposited by the incoming air during the preceding ten-minute switch period. It finally exhausts to atmosphere through the switch valve.

The product liquid oxygen is withdrawn from the bottom of the low-pressure column. It passes through the subcooler where it is subcooled by the effluent waste air to prevent or reduce "flash" losses resulting from expansion into the reciprocating oxygen pump, or into an external receiver. In the pump its pressure is elevated to 4000 PSIG and it is discharged through a heat exchanger or vaporizer in the discharge line of the third-stage blower where it is warmed to ambient temperature.

In the case of producing nitrogen the other vapor stream from the phase separator is expanded through a valve from high-pressure-air pressure to high-pressure column pressure, which is approximately 52.2 PSIA. The vapor enters the high-pressure nitrogen column which contains a number of bubble-cap pans of conventional design. The ascending vapor comes into intimate contact with liquid descending on the pans. This intimate contact of vapor and liquid on each pan results in a gradual vaporization of the more volatile constituent, nitrogen and a condensation of the less volatile constituent, oxygen, which is expanded into the low pressure column. The ascending vapor enters the condenser where it is condensed to a liquid nitrogen product by the crude oxygen product which surrounds the tubes on the low pressure column side of the condenser. As in the case of oxygen production a small noncondensable stream is removed from the dome of the condenser to prevent blanketing of the condenser surface.

The low pressure column consists essentially of a condenser and shell. The expanded crude oxygen from the high pressure column and the expanded liquid stream

from the product pump racks are introduced into the low pressure column side of the condenser. These streams are vaporized by the condensing nitrogen in the high pressure column and the resulting vapor passes through several entrainment trays above the condenser in the low pressure column.

The waste vapor from the low pressure column passes through the subcooler. After passing through the subcooler, it combines with the turbo expander exhaust and enters the air liquefier where it liquefies a portion of the incoming high-pressure air. From the air liquefier it passes through the heat exchanger where it both cools the incoming air to saturation temperature, and absorbs the moisture and carbon dioxide which were deposited by the incoming air during the preceding ten-minute switch period. It finally exhausts to atmosphere through the switch valve.

The product liquid nitrogen is withdrawn from the bottom of the condenser. It passes through the subcooler into the reciprocating nitrogen pump, or into an external receiver. In the pump its pressure is elevated to 4000 PSIA and it is discharged through a heat exchanger or vaporizer in the discharge line of the third-stage blower where it is warmed to ambient temperature.

Pressure gauges, liquid-level gauges and temperature indicators are located throughout the system as necessary to serve as operating aids. In addition, all circuits in the cycle are protected against excess pressure by means of pop safety valves.

After 150 or more hours of operation, accumulation of moisture and carbon dioxide deposits may require that the generator be defrosted or derimed. To accomplish this, numerous outlets are provided at desired locations to vent the defrost air to atmosphere.

Should ambient air penetrate the air separator insulation jacket, its moisture content would be deposited upon the cold surfaces of the components and also upon the cold fiberglass insulation. To prevent this, the insulation jacket is put under a slight, positive pressure by means of a small stream of dry, nitrogen-rich air which is tapped from the turbo expander supply line and warmed in a coil inside the condensate trap.

## SECTION II

### ELECTRIC POWER AND CONTROL

The electric power and control circuits of this generator are pictured in Figure 5, Air Products, Incorporated Drawing No. 42563, Single Line Wiring Diagram.

The electric power required by the product pumps, the hydrocarbon adsorber reactivation heater, switch valve timing control, and lighting is furnished by a 18.7 Kva, 120/208 volt, 3 phase, 4 wire, 60 cycle synchronous generator with direct connected exciter and automatic voltage regulator as an integral part of its frame. This alternating current generator is driven at 1800 RPM through a V-belt drive by one of the diesel engines in the air compressing section.

Power is distributed throughout the trailer from a control center which contains a three-phase main service circuit breaker for the circuit from the a-c generator; a combination three-phase starter for the pump motors; a three-phase circuit breaker and control for the hydrocarbon adsorber reactivation heater; and branch circuit breakers for the 120 volt single phase timing control, lighting, and power receptacle circuits.

Emergency lighting, alarm circuits for diesel engine cooling water and oil pressure indication, and emergency engine shut-down control are energized from the 24-volt d-c storage battery bank furnished for starting the diesel engines. This bank can be charged by one of the generators on either of two of the engines.

### SECTION III

#### THERMODYNAMIC CALCULATIONS

The sources of thermodynamic data for this report were: Miller & Sullivan, U. S. Bureau of Mines, Mollier Charts of 1928; and V. C. Williams, Northwestern University.

The material balance of this cycle is based upon the following composition of atmospheric air: 21% oxygen, 78% nitrogen, and 1% argon.

The term "standard cubic feet per minute", abbreviated SCFM, as used in this report means one cubic foot of gas at the standard conditions of 70°F and 14.7 PSIA.




Figure 6 Liquid Nitrogen Generator Heat Balance

Refrigeration, R

The refrigeration available results from the expansion of approximately 75% of the incoming air from 112 PSIA to 21 PSIA. For the expander to have an adiabatic efficiency of 72% the assumed inlet temperature is -240°F

$$\begin{aligned} H_1 &= \text{Enthalpy At Inlet Conditions 112 PSIA } -240^\circ\text{F} \\ &= 104.50 \text{ Btu/Lb} \end{aligned}$$

$$\begin{aligned} H_0 \text{ isen} &= \text{Enthalpy at Expander Exhaust for 100% Expander Efficiency} \\ &= 85.58 \text{ Btu/Lb} \end{aligned}$$

$H_o \text{ act}$  = Enthalpy At Actual Exhaust Conditions

$$= 90.93 \text{ Btu/Lb}$$

$$\text{Efficiency} = \frac{H_1 - H_o \text{ act}}{H_1 - H_o \text{ is en}} \times 100$$

$$= \frac{104.5 - 90.93}{104.5 - 85.58} \times 100 = 71.72\%$$

This checks the anticipated value

$$R = H_1 - H_o \text{ act}$$

$$= 104.5 - 90.93$$

$$= 13.57 \text{ Btu/Lb}$$

Since only 75% of the incoming air is to be expanded

$$R = 0.75 \times 13.57$$

$$= 10.18 \text{ Btu/Lb}$$

For 100 lbs.

$$R = 1018 \text{ Btu}$$

Enthalpy of Incoming Air,  $H_A$

At the conditions of 100 PSIG & 80°F the heat content of 100 lbs. of entering air will be

$$H_A = 18,430 \text{ Btu}$$

Enthalpy of Liquid Nitrogen,  $H_N$

At the conditions of 14.7 PSIA and -298°F the enthalpy of liquid nitrogen is (Equivalent of 3.55 ATM SAT.)

$$H_N = 12.02 \text{ Btu/Lb}$$

For x lbs. the heat content will be

$$H_N = 12.02 x$$

Heat Leak, H. L.

The anticipated heat leak is taken as

$$H.L. = 1.5 \text{ Btu/Lb or } 150 \text{ Btu for 100 lbs.}$$

Enthalpy of the Effluent Waste Air,  $H_W$

At the conditions of 1 FSIG & 72°F the enthalpy of the waste air is equal to the sum of the enthalpies of the constituents

The enthalpy of nitrogen at these conditions is

$$H_N = 183.5 \text{ Btu/Lb.}$$

Since 78-x pounds of  $N_2$  are exhausted as waste in this case

$$H_N = 183.50 (78-x)$$

$$H_N = 14,313 - 183.5x \text{ Btu}$$

The enthalpy of the oxygen under these conditions is

$$H_O = 181.20 \text{ Btu/Lb.}$$

Since all the oxygen is waste

$$H_O = 22 \times 181.20$$

$$H_O = 3,986 \text{ Btu}$$

$$H_W = H_N + H_O$$

$$= 14,313 - 183.5x + 3,986$$

$$H_W = 18,299 - 183.5x$$

Total Heat Balance

The total heat balance will be

$$H_A + H.L. = H_W + R + H_V$$

$$18,430 + 150 = 18,299 - 183.5x + 12.02x + 1018$$

$$x = 4.30 \text{ pounds } N_2 \text{ produced per 100 pounds Air}$$

Since it is impossible to get sufficient subcooling 14.0% of the liquid nitrogen produced will flash.

The air required for 2 tons per day liquid production is

$$Q = 2 \text{ (Tons/Day)} \times 2000 \text{ (Lbs)} \times \frac{1 \text{ (Days)}}{24 \text{ (Hr)}} \times \frac{1 \text{ (Hr)}}{60 \text{ (Min)}} \times \frac{1 \text{ (CuFt)}}{0.075 \text{ (Lbs)}} \times \frac{1}{0.0430} \times \frac{1}{0.86}$$

$$Q = 1002 \text{ Assuming a 3% reversal loss}$$

$$Q = 1032 \text{ Say 1035 SCFM}$$

## GENERATOR MATERIAL BALANCE

### Point 1-N Standard Intake Conditions for Air Compressor

Pressure 14.7 PSIA  
Temperature 70°F  
Fluid State Superheated Vapor  
Fluid Flow Rate

$$W_1 = 1035 \times 0.075 \times 60 \times \frac{1}{28.9}$$

$$= 161.16 \frac{\text{lb} - \text{Mols}}{\text{Hr}}$$

Composition

Flow x Concentration = Composition

$$W_{O_2} = 0.21 \times 161.16$$

$$= 33.84 \text{ Mols/Hr}$$

$$W_{N_2} = 0.78 \times 161.16$$

$$= 125.71 \text{ Mols/Hr}$$

$$W_A = 0.01 \times 161.16$$

$$= 1.61 \text{ Mols/Hr}$$

Enthalpy

At 14.7 PSIA and 70°F

$$H_1 = 182.74 \text{ Btu/Lb}$$

### Point 2-N Discharge for Air Compressor

Pressure 114.7 PSIA  
Temperature 80°F  
Fluid State Superheated Vapor  
Fluid Flow Rate

The 3% switch loss is eliminated for the purpose of calculating a heat balance.

$$W_2 = 156.02 \text{ Mols/Hr}$$

Composition

$W_{O_2} = 32.76$  Mols/Hr

$W_{N_2} = 121.70$  Mols/Hr

$W_A = 1.56$  Mols/Hr

Enthalpy

At 114.7 PSIA and 80°F

$H_2 = 184.30$  Btu/Lb

Point 3-N High Pressure Air Leaving Heat Exchanger

Pressure

114.7 PSIA

Temperature

-272°F

The air leaving the exchanger will be a saturated vapor at  
114.7 PSIA

Fluid State

Saturated Vapor

Fluid Flow Rate

$W_3 = 156.02$  Mols/Hr

Composition

$W_{O_2} = 32.76$  Mols/Hr

$W_{N_2} = 121.70$  Mols/Hr

$W_A = 1.56$  Mols/Hr

Enthalpy

At 114.7 PSIA and -272°F

$H_3 = 95.79$  Btu/Lb

Point 4-N High Pressure Air Leaving Air Liquifier

Pressure

114.7 PSIA

Temperature

-272°F

Fluid State

The liquid requirement of the air entering the liquifier is the  
sum of the liquid equivalent of the product takeoff, the liquid

equivalent of the heat loss, and the liquid equivalent of the expansion loss.

Product Liquid Equivalent

The latent heat of nitrogen at 52.2 PSIA is  $H = 78.00 \text{ Btu/Lb}$

On the basis of 4.3% recovery

$$H = 3.35 \text{ Btu/Lb}$$

Heat Loss Liquid Equivalent

$$H_{H.L.} = 1.5 \text{ Btu/Lb}$$

Expansion Loss Liquid Equivalent

The enthalpy drop at saturated vapor conditions resulting from the expansion of incoming air from 114.7 PSIA to 21 PSIA is

$$H_{Exp} = 95.79 - 90.93$$

$= 4.86 \text{ Btu/Lb}$  Since only 25% of the incoming air is to be expanded

$$H_{Exp} = 0.25 \times 4.86$$

$$H_{Exp} = 1.22 \text{ Btu/Lb}$$

The total liquid requirement enthalpy drop is

$$H = H_{T.O.} + H_{H.L.} + H_{Exp}$$

$$= 3.35 + 1.50 + 1.22$$

$$= 6.07 \text{ Btu/Lb}$$

The latent heat of vaporization of air at 114.7 PSIA

$$L.H. = 95.79 - 22.61$$

$$= 73.18 \text{ Btu/Lb}$$

$$\text{Liquid Requirement} = H/L.H. \times 100$$

$$\text{Liquid Requirement} = 6.07/73.18 \times 100$$

$$= 8.29\%$$

Hence the fluid state will be 8.29% liquid and 91.71% vapor

Composition

Same as Point 3

$$W_{O_2} = 32.76 \text{ Mols/Hr}$$

$$W_{N_2} = 121.70 \text{ Mols/Hr}$$

$$W_A = 1.56 \text{ Mols/Hr}$$

Enthalpy

At 114.7 PSIA and -272°F

$$H_A = 89.72 \text{ Btu/Lb}$$

Point 5-W High Pressure Air Leaving the Phase Separator and Entering the Expansion Valve

Entering the 7.8 atmosphere equilibrium curve for oxygen and nitrogen at -272° or 104.3°K for 21 mol percent oxygen

$$\text{Total Mols} = \text{Mols Liquid} + \text{Mols Vapor}$$

$$0.21 = 0.0829 (0.366) + 0.9171 (0.196)$$

$$0.21 = 0.0303 + 0.1798$$

$$0.21 = 0.2101$$

$$\text{Mols Oxygen Vapor} = 0.1798 \times 156.02$$

$$W_{O_2} = 28.04 \text{ Mols/Hr}$$

$$\text{Mols Oxygen Liquid} = 0.0303 \times 156.02$$

$$W_{O_2} = 4.72 \text{ Mols/Hr}$$

The amount of air entering the phase separator which is expanded into the high pressure column through the A1 expansion valves is

$$100 - 75 - 8.29 = 16.71\%$$

Pressure

114.7 PSIA

Temperature

-272°F

Fluid State

Saturated Vapor


Fluid Flow Rate

$$W_5 = 0.1671 \times 156.02$$

$$= 26.07 \text{ Mols/Hr}$$

133-11 KROPP & KROPP CO.  
10 x 10 to the 1/2 inch, 216 lines per inch.  
Aug 19 1954

WADC TR 54-19 PT 1



Composition

$$W_{O_2} = 26.07 \times 0.196$$

$$= 5.11 \text{ Mols/Hr}$$

$$W_A = 1/21 \times 5.11$$

$$= 0.24$$

$$W_{N_2} = 26.07 - 5.11 - 0.24$$

$$= 20.72 \text{ Mols/Hr}$$

Enthalpy

At 114.7 PSIA and -272°F

$$H_5 = 95.79 \text{ Btu/Lb}$$

Point 6-N High Pressure Air Entering High Pressure Nitrogen Column

Pressure

52.2 PSIA

Temperature

-282.5°F

Fluid State

Superheated Vapor

Fluid Flow Rate

Same as Point 5

$$W_6 = 26.07 \text{ Mols/Hr}$$

Composition

Same as Point 5

$$W_{O_2} = 5.11 \text{ Mols/Hr}$$

$$W_{N_2} = 20.72 \text{ Mols/Hr}$$

$$W_A = 0.24 \text{ Mols/Hr}$$

Enthalpy

At 52.2 PSIA and -282.5°F

$$H_6 = 95.79 \text{ Btu/Lb}$$

Point 7-N High Pressure Air Leaving Phase Separator and Entering Cold Heat Exchanger

The pressure and temperature are the same as Point 5 with the flow and composition proportional to the division of the total vapor phase leaving the phase separator.

Pressure 114.7 PSIA  
Temperature -272°F  
Fluid State Saturated Vapor  
Fluid Flow Rate

$$W_7 = 0.75 \times 156.02$$
$$= 117.02 \text{ Mols/Hr}$$

Composition

$W_{O_2}$  = Total  $O_2$  Vapor leaving separator - Oxygen to Column

$$W_{O_2} = 28.04 - 5.11$$
$$= 22.93 \text{ Mols/Hr}$$

$$W_A = 1/21 \times 22.93$$
$$= 1.09 \text{ Mols/Hr}$$

$$W_{N_2} = 117.02 - 1.09 - 22.93$$
$$= 93.00 \text{ Mols/Hr}$$

Enthalpy

At 114.7 PSIA and -272°F

$$H_7 = 95.79 \text{ Btu/Lb}$$

Point 8-W High Pressure Air Entering Turbo Expander

Stream 7 in passing through the heat exchanger will undergo a slight pressure drop and rise in temperature. This warm-up will increase the expander efficiency.

Pressure 112 PSIA  
Temperature -240°F  
Fluid State Superheated Vapor  
Fluid Flow Rate Same as Point 7  
 $W_8 = 117.02 \text{ Mols/Hr}$   
Composition Same as Point 7

$$W_{O_2} = 22.93 \text{ Mols/Hr}$$

$$W_{N_2} = 93.00 \text{ Mols/Hr}$$

$$W_A = 1.09 \text{ Mols/Hr}$$

#### Enthalpy

At 112 PSIA and  $-240^\circ\text{F}$

$$H_8 = 104.50 \text{ Btu/lb}$$

#### Point 9-N Low Pressure Air Leaving the Expander and Feeding the Low Pressure Column

No flow is demanded through Point 9 since the only purpose of such a flow is to give advantage to the low pressure column in so far as oxygen production is concerned.

#### Point 10-N Expander Exhaust Stream into Air Liquifier

Pressure	21 PSIA
Temperature	$-306^\circ\text{F}$
Fluid State	Saturated Vapor
Fluid Flow Rate	Same as Point 8

$$W_{10} = 117.02 \text{ Mols/Hr}$$

Composition	Same as Point 8
-------------	-----------------

$$W_{O_2} = 22.93 \text{ Mols/Hr}$$

$$W_{N_2} = 93.00 \text{ Mols/Hr}$$

$$W_A = 1.09 \text{ Mols/Hr}$$

Enthalpy	90.93 Btu/lb
----------	--------------

#### Point 11-N Air Stream Feeding Air Liquifier

Pressure	21 PSIA
Temperature	$-306^\circ\text{F}$
Fluid State	Saturated Vapor
Fluid Flow Rate	

The flow will be stream 4 minus the product take-off

$$W_{11} = 156.02 - 2 \times 2000/0.86 \times 28 \times 24$$

$$W_{11} = 149.10 \text{ Mols/Hr}$$

### Composition

Referring to compositions at Point 14, Point 6 and Point 10.

$$W_{O_2} = 5.11 + 4.72 + 22.93 - 0.04$$

$$= 32.72 \text{ Mols/Hr}$$

$$W_{N_2} = 20.72 + 7.99 + 93.00 - 6.84$$

$$= 114.87 \text{ Mols/Hr}$$

$$W_A = 0.24 + 0.22 + 1.09 - 0.04$$

$$= 1.51 \text{ Mols/Hr}$$

### Enthalpy

Combination of Points 19 and 10

$$= \frac{90.93 \times 117.02 + 91.10 \times 32.08}{149.10} = 90.97 \text{ Btu/Lb}$$

Point 12-N Air Leaving Air Liquifier and Entering Cold Heat Exchanger

### Pressure

19 PSIA

### Temperature

All of the latent heat of the liquified air is taken by this stream.

$$(95.79 - 89.72) \quad 156.02/149.10 = 6.34$$

$$6.34 + 90.97 = 97.31 \text{ Btu/Lb}$$

$$T_{12} = -283.60^\circ\text{F}$$

### Fluid State

Superheated Vapor

### Fluid Flow Rate

Same as Point 11

$$W_{12} = 149.10 \text{ Mols/Hr}$$

### Composition

Same as Point 11

$$W_{O_2} = 32.72 \text{ Mols/Hr}$$

$$W_{N_2} = 114.87 \text{ Mols/Hr}$$

$$W_A = 1.51 \text{ Mols/Hr}$$

### Enthalpy

At 19 PSIA and  $-283.6^{\circ}\text{F}$  the enthalpy is

$$H_{12} = 97.31 \text{ Btu/Lb}$$

### Point 13-N Waste Air Leaving Warm Heat Exchanger

Pressure 14.7 PSIA

Temperature  $72^{\circ}\text{F}$

Fluid State Superheated Vapor

Fluid Flow Rate Same as Point 12

$$W_{13} = 149.10 \text{ Mols/Hr}$$

Composition Same as Point 12

$$W_{O_2} = 32.72 \text{ Mols/Hr}$$

$$W_{N_2} = 114.87 \text{ Mols/Hr}$$

$$W_A = 1.51 \text{ Mols/Hr}$$

### Enthalpy

At 14.7 PSIA and  $72^{\circ}\text{F}$

$$H_{13} = 182.97 \text{ Btu/Lb}$$

### Point 14-N High Pressure Liquid Leaving Phase Separator

Pressure 114.7 PSIA

Temperature  $-275.6^{\circ}\text{F}$

Fluid State Saturated Liquid

Fluid Flow Rate

$$W_{14} = 0.0829 \times 156.02$$

$$= 12.93 \text{ Mols/Hr}$$

### Composition

$$W_{O_2} = 4.72 \text{ Mols/Hr}$$

$$W_A = 4.72 \times 1/21$$

$$W_A = 0.22 \text{ Mols/Hr}$$

$$W_{N_2} = 12.93 - 0.22 - 4.72$$

$$W_{N_2} = 7.99 \text{ Mols/Hr}$$

#### Enthalpy

At 114.7 PSIA and -275.6°F

$$H_{14} = 22.55 \text{ Btu/Lb}$$

#### Point 15-N Low Pressure Air Leaving Expansion Valve and Entering Low Pressure Column

The liquid air is expanded to the pressure at the top of the low pressure column at constant enthalpy.

Pressure 21 PSIA

Temperature -304.3°F

Fluid State

The expansion of saturated liquid from 114.7 PSIA to 21 PSIA results in

79.05% Liquid

20.95% Vapor

Fluid Flow Rate

Same as Point 14

$$W_{15} = 12.93 \text{ Mols/Hr}$$

Composition

$$W_{O_2} = 4.72 \text{ Mols/Hr}$$

$$W_{N_2} = 7.99 \text{ Mols/Hr}$$

$$W_A = 0.22$$

#### Enthalpy

At 21 PSIA and -304.3°F

$$H_{15} = 22.55 \text{ Btu/Lb}$$

Point 16 Liquid Air Leaving High Pressure Column

This is the result of liquification of Stream 6 minus the product take-off.

Pressure 52.2 PSIA  
Temperature -291.9°F  
Fluid State Saturated Liquid  
Fluid Flow Rate

$$W_{16} = 26.07 - 6.92 = 19.15 \text{ Mols/Hr}$$

Composition

$$W_{O_2} = 5.11 - 0.005 \times \frac{2000 \times 2}{24 \times 28 \times .86} = 5.07 \text{ Mols/Hr}$$

$$W_{N_2} = 20.72 - 6.84 = 13.88$$

$$W_A = 0.24 - 0.04 = 0.20$$

Enthalpy

At 52.2 PSIA and -291.9°F

$$H_{16} = 12.77 \text{ Btu/Lb}$$

Point 17 Liquid Air Entering Low Pressure Column

Pressure 21 PSIA  
Temperature -304.3°F  
Fluid State Liquid and Vapor

The expansion of 52.2 PSIA saturated liquid to 21 PSIA results in 90.40% liquid and 9.60% vapor.

Fluid Flow Rate Same as Point 16

$$W_{17} = 19.15 \text{ Mols/Hr}$$

Composition

Same as Point 16

$$W_{O_2} = 5.07 \text{ Mols/Hr}$$

$$W_{N_2} = 13.88 \text{ Mols/Hr}$$

$$W_A = 0.20 \text{ Mols/Hr}$$

### Enthalpy

At 21 PSIA and  $-304.3^{\circ}\text{F}$

$$H_{17} = 12.77 \text{ Btu/Lb}$$

### Point 18 Waste Air Leaving Low Pressure Column

The waste air leaving the low pressure column will be saturated vapor at the pressure at the top of the column.

Pressure	21.5 PSIA
Temperature	$-304.3^{\circ}\text{F}$
Fluid State	Saturated Vapor
Fluid Flow Rate	

Stream 18 equals stream 19 which equals stream 4 minus stream 10 minus the product take-off

$$W_{18} = 156.02 - 117.02 - \frac{2 \times 2000}{24 \times 28} \times \frac{1}{0.84} \text{ (Due to product flash)}$$

$$W_{18} = 32.08 \text{ Mols/Hr}$$

### Composition

Stream 15 + stream 17

$$W_{O_2} = 5.07 + 4.72 = 9.79 \text{ Mols/Hr}$$

$$W_{N_2} = 7.99 + 13.88 = 21.87 \text{ Mols/Hr}$$

$$W_A = 0.22 + 0.20 = 0.42 \text{ Mols/Hr}$$

### Enthalpy

At 21 PSIA and  $-304.3^{\circ}\text{F}$

$$H_{18} = 91.10 \text{ Btu/Lb}$$

### Point 19-N Waste Air Leaving Subcooler (Same as Point 18)

Pressure	21 PSIA
Temperature	$-304.3^{\circ}\text{F}$

Fluid State

Saturated Vapor

Fluid Flow Rate

Same as Point 18

$$W_{19} = 32.08 \text{ Mols/Hr}$$

Composition

Same as Point 18

$$W_{O_2} = 9.79 \text{ Mols/Hr}$$

$$W_{N_2} = 21.87 \text{ Mols/Hr}$$

$$W_A = 0.42 \text{ Mols/Hr}$$

Enthalpy

As shown

$$H_{19} = 91.10 \text{ Btu/Lb}$$

Point 20 Liquid Nitrogen Entering Subcooler

Pressure

52.2 PSIA

Temperature

-298°F

Fluid State

Saturated Liquid

Fluid Flow Rate

$$W = \frac{2 \times 2000}{24 \times 0.86 \times 28}$$

$$W_{20} = 6.92 \text{ Mols/Hr}$$

Composition

$$W_{N_2} = 6.92 \times 0.99 = 6.84 \text{ Mols/Hr}$$

$$W_{O_2} = 0.04 \text{ Mols/Hr}$$

$$W_A = 0.04 \text{ Mols/Hr}$$

It is assumed that the impurity is equally divided between oxygen and argon.

Enthalpy

At 52.2 PSIA and -298°F

$$H_{20} = 12.02 \text{ Btu/Lb}$$

Point 21-N Liquid Nitrogen Take-Off

Pressure

14.7 PSIA

Temperature

-298°F

Fluid State

14% Vapor

86% Liquid

Fluid Flow Rate

$$W_{21} = 6.92 \text{ Mols/Hr}$$

Composition

$$W_{N_2} = 6.84 \text{ Mols/Hr}$$

$$W_{O_2} = 0.04 \text{ Mols/Hr}$$

$$W_A = 0.04 \text{ Mols/Hr}$$

Vapor

$$W = 0.97 \text{ Mols/Hr}$$

Liquid

$$W = 5.95 \text{ Mols/Hr}$$

Enthalpy

At 14.7 PSIA and -298°F

$$H = 12.02 \text{ Btu/Lb}$$

# Summary

The conditions calculated for the various points in the flow diagram are summarized below.

Pt. No.	Pressure (PSIA)	Temp. (°F)	Composition (Lb Moles/Hr)				Phase	Enthalpy Btu/Lb	Total Heat Btu/Hr
			O <sub>2</sub>	N <sub>2</sub>	A	Total			
1-N	14.7	70	33.84	125.71	1.61	161.16	Vapor	182.74	851,116
2-N	114.7	80	32.76	121.70	1.56	156.02	Vapor	184.30	831,005
3-N	114.7	-272	32.76	121.70	1.56	156.02	Vapor	95.79	431,915
4-N	114.7	-272	32.76	121.70	1.56	156.02	Liq&Vap	89.72	404,546
5-N	114.7	-272	5.11	20.72	0.24	26.07	Vapor	95.79	72,170
6-N	52.2	-282.5	5.11	20.72	0.24	26.07	Vapor	95.79	72,170
7-N	114.7	-272	22.93	93.00	1.09	117.02	Vapor	95.79	323,950
8-N	112.0	-240	22.93	93.00	1.09	117.02	Vapor	104.50	353,406
10-N	21.0	-306	22.93	93.00	1.09	117.02	Vapor	90.93	307,514
11-N	21.0	-306	32.72	114.87	1.51	149.10	Vapor	90.97	392,545
12-N	19.0	-283.6	32.72	114.87	1.51	149.10	Vapor	97.31	419,914
13-N	14.7	72	32.72	114.87	1.51	149.10	Vapor	182.97	789,548
14-N	114.7	-275.6	4.72	7.99	0.22	12.93	Liquid	22.55	8,426
15-N	21.5	-304.3	4.72	7.99	0.22	12.93	Liq&Vap	22.55	8,426
16	52.2	-292.9	5.07	13.88	0.20	19.15	Liquid	12.77	7,067
17	21.5	-304.3	5.07	13.88	0.20	19.15	Liq&Vap	12.77	7,067
18	21.5	-304.3	9.79	21.87	0.42	32.08	Vapor	91.10	85,031
19-N	21.0	-304.3	9.79	21.87	0.42	32.08	Vapor	91.10	85,031
20	52.2	-298	0.04	6.84	0.04	6.92	Liquid	12.02	2,329
21-N	14.7	-298	0.04	6.84	0.04	6.92	Liq&Vap	12.02	2,329

### Heat Balance

For any heat balance  $Q_{in} = Q_{out}$  where  $Q = W(\text{Lbs/Hr}) \times H(\text{Btu/Lb})$

### Heat Exchange Balance

$Q_{in} = Q_2 + Q_7 + Q_{12}$  where  $Q_2$  is corrected to allow for the loss due to reversal

$$= 831,005 + 323,950 + 419,914$$

$$= 1,574,869$$

$$Q_{out} = Q_3 + Q_8 + Q_{13}$$

$$= 431,915 + 353,406 + 789,548$$

$$= 1,574,869$$

### Air Liquifier Balance

$$Q_{in} = Q_3 + Q_{11}$$

$$= 431,915 + 392,545$$

$$= 824,460$$

$$Q_{out} = Q_4 + Q_{12}$$

$$= 404,546 + 419,914$$

$$= 824,460$$

### Phase Separator Heat Balance

$$Q_{in} = Q_4$$

$$= 404,546$$

$$Q_{out} = Q_5 + Q_7 + Q_{14}$$

$$= 72,170 + 323,950 + 8,426$$

$$= 404,546$$

### Turbo Expander Heat Balance

$$Q_{in} = Q_8$$

$$= 353,406$$

$$Q_{out} = Q_{10} + Q_{work}$$

$$= 307,514 + Q_{work}$$

$$Q_{work} = 353,406 - 307,514$$

$$= 45,892$$

or

$$= 18.04 \text{ H.P.}$$

### Distillation Column Heat Balance

$$Q_{in} = Q_6 + Q_{15} + Q_{\text{Heat Leak}}$$

$$= 72,170 + 8,426 + (156.02 \times 1.5 \times 28.9)$$

$$= 87,360$$

$$Q_{out} = Q_{18} + Q_{20}$$

$$= 85,031 + 2,329$$

$$= 87,360$$

## Overall Heat Balance

### Liquid Oxygen Production




Figure 8 Liquid Oxygen Generator Heat Balance

#### Enthalpy of the Liquid O<sub>2</sub> Drained, H<sub>O</sub>

At the conditions of 14.7 PSIA and -298°F the enthalpy of the liquid O<sub>2</sub> is

$$H_O = 8.89 \text{ Btu/Lb}$$

For x Lbs. drained

$$H_O = 8.89x \text{ Btu}$$

#### Enthalpy of the Effluent Waste Air, H<sub>W</sub>

At the conditions of 1 PSIG and 72°F the enthalpy of the waste air is equal to the sum of the enthalpies of the constituents.

The enthalpy of nitrogen at these conditions is

$$H_{NW} = 183.5 \text{ Btu/Lb}$$

All of the nitrogen contained in the intake air will be waste thus

$$H_{NW} = 183.5 \times 79 = 14,497 \text{ Btu}$$

The enthalpy of oxygen at these conditions is

$$H_{OW} = 181.2 \text{ Btu/Lb}$$

The oxygen contained in the waste air will be

$$(21 - x) \text{ Lbs/100 Lbs of Air Feed}$$

$$H_{OW} = 181.2 (21 - x)$$

$$= 3805 - 181.2x \text{ Btu}$$

$$H_W = H_{NW} + H_{OW} = 14,497 + 3,805 - 181.2x$$

$$H_W = 18,302 - 181.2x \text{ Btu}$$

#### Total Heat Balance

The total heat balance will be

$$H_A + H.L. = H_W + R + H_Q$$

$$18,430 + 150 = 18,302 - 181.2x + 1,018 + 8.89x$$

$$740 = 172.31x$$

$$x = 4.29 \text{ Lbs } O_2/100 \text{ Lbs Air Feed}$$

This indicates a 4.29% recovery by weight. For two tons per day the required air intake will be

$$Q = \frac{2 \text{ Tons}}{\text{Days}} \times \frac{2000 \text{ Lbs}}{1 \text{ Ton}} \times \frac{1 \text{ Days}}{24 \text{ Hr}} \times \frac{1 \text{ Hrs}}{60 \text{ Min}} \times \frac{1}{0.075 \text{ Lb}} \times \frac{1 \text{ Cu Ft}}{0.0429}$$

$$Q = 863 \text{ SCFM}$$

Assuming a 3% loss during reversal

$$0.03 \times 863 = 25.9$$

$$Q = 863 + 25.9 = 889 \text{ say } 890 \text{ SCFM}$$

Since the expander requires 750 SCFM and the compressors are capable of 1000 SCFM

$$Q = 1000$$

$$\frac{1000 \times 24 \times 60 \times 0.075 \times 0.0429}{2000}$$

$$\text{Production} = 2.32 \text{ T/D}$$

$$Q \text{ including Reversal Loss} = 1030 \text{ SCFM}$$

# Summary: Liquid Oxygen Production

As in the liquid nitrogen cycle the following points are the result of the thermodynamic analysis:

Pt. No.	Pressure (PSIA)	Temp. (°F)	Composition (Lb Mols/Hr)				Phase	Enthalpy Btu/lb	Total Heat Btu/Hr
			O <sub>2</sub>	N <sub>2</sub>	A	Total			
*1-0	14.7	70	32.70	121.45	1.56	155.71	Vapor	182.74	822,333
2-0	114.7	80	32.70	121.45	1.56	155.71	Vapor	184.30	829,354
3-0	114.7	-272	32.70	121.45	1.56	155.71	Vapor	95.79	431,039
4-0	114.7	-272	32.70	121.45	1.56	155.71	Liq&Vap	89.22	401,492
5-0	114.7	-272	4.86	19.85	0.23	24.94	Vapor	95.79	69,095
22	89	-276	4.86	19.85	0.23	24.94	Vapor	95.79	69,095
7-0	114.7	-272	22.77	92.93	1.08	116.78	Vapor	95.79	323,286
8-0	112.0	-240	22.77	92.93	1.08	116.78	Vapor	104.5	352,681
10-0	21	-306	22.77	92.93	1.08	116.78	Vapor	90.93	306,883
11-0	21	-305	26.69	121.45	1.53	149.67	Vapor	90.56	390,149
12-0	19	-281	26.69	121.45	1.53	149.67	Vapor	97.45	419,696
13-0	14.7	72	26.69	121.45	1.53	149.67	Vapor	182.97	788,598
14-0	114.7	-275.6	5.10	8.64	0.24	13.98	Liquid	22.55	9,111
15-0	21	-304.3	5.10	8.64	0.24	13.98	Liq&Vap	22.55	9,111
23	89	-282	4.86	19.85	0.23	24.94	Liquid	19.18	13,624
24	21	-304.3	4.86	19.85	0.23	24.94	Liq&Vap	19.18	13,824
25	21	-311.5	3.92	28.52	0.45	32.89	Vapor	86.96	82,757
19-0	21	-305.0	3.92	28.52	0.45	32.89	Vapor	87.48	83,248
26	21	-291	6.01	0.00	0.03	6.04	Liquid	11.43	2,209
21-0	14.7	-298	6.01	0.00	0.03	6.04	Liquid	8.89	1,718

NOTE: 3% Reversal Loss not included in Point 1 Tabulation

## Overall Heat Balance

### Gaseous Nitrogen Production




Figure 9 Gaseous Nitrogen Heat Balance

#### Enthalpy of the Liquid N<sub>2</sub> Pumped, H<sub>N</sub>

At the condition of 4014.7 PSIA the enthalpy of the pumped nitrogen is

$$H_N = 12.02 \text{ Btu/Lb}$$

For x Lbs pumped

$$H_N = 12.02x \text{ Btu}$$

#### Enthalpy of the Effluent Waste Air, H<sub>w</sub>

At the conditions of 1 PSIG and 72°F the enthalpy of the waste air is equal to the sum of the enthalpies of the constituents.

$$H_{wW} = 183.5 \text{ Btu/Lb}$$

The nitrogen contained in the waste air will be (78 - x) Lbs/100 Lbs of Air Feed thus

$$H_{wW} = (78 - x) 183.5$$

$$= 14,313 - 183.5x$$

The enthalpy of oxygen at these conditions is

$$H_{OW} = 181.2 \text{ Btu/Lb}$$

All of the oxygen contained in the intake air will be waste hence

$$H_{OW} = 181.2 \times 22$$

$$= 3,986 \text{ Btu}$$

$$H_W = H_{NW} + H_{OW} = 14,313 - 183.5x + 3,986$$

$$H_W = 18,299 - 183.5x$$

#### Pump Input

It is estimated that the pump input to the circuit is 2 H.P. or

$$2 \left( \frac{\text{HP}}{1} \right) \times 2544 \left( \frac{\text{Btu}}{\text{HP-Hr}} \right) \times \frac{1}{166.6} \left( \frac{\text{Hrs}}{\text{Lb N}_2} \right) = 30.53 \text{ Btu/Lb N}_2$$

Since there are to be  $x$  Lbs of nitrogen pumped per 100 Lbs of air feed

$$H_p = 30.53x \text{ Btu}$$

#### Total Heat Balance

The total heat balance will be

$$H_A + H.L. + H_p = H_W + R + H_N$$

$$18,430 + 150 + 30.53x = 18,299 - 183.5x + 1,018 + 12.02x$$

$$18,580 + 30.53x = 19,317 - 171.48x$$

$$202.01x = 737$$

$$x = 3.65 \text{ Lbs N}_2/100 \text{ Lbs Air Feed}$$

This indicates a 3.65% recovery by weight. For two tons per day the required air intake will be

$$Q = 2 \frac{\text{Tons}}{\text{Day}} \times \frac{2000}{1} \frac{\text{Lbs}}{\text{Ton}} \times \frac{1}{24} \frac{\text{Days}}{\text{Hr}} \times \frac{1}{60} \frac{\text{Hrs}}{\text{Min}} \times \frac{1}{0.075} \frac{\text{Cu Ft}}{\text{Lb}} \times \frac{1}{0.0365}$$

$$Q = 1015 \text{ SCFM}$$

Since 3% is assumed to be Reversal Loss

$$0.03 \times 1015 = 30$$

$$\text{Total Air Required} = 1045 \text{ S.C.F.M.}$$

# Summary: Gaseous Nitrogen Production

As in the liquid nitrogen cycle the following points are the result of the thermodynamic analysis:

Pt.No	Pressure (PSIA)	Temp. (°F)	Composition (Lb Mols/Hr)				Phase	Enthalpy Btu/Lb	Total Heat Btu/Hr
			O <sub>2</sub>	N <sub>2</sub>	A	Total			
*1-PN	14.7	70	33.19	123.27	1.58	158.04	Vapor	182.74	859,355
2-PN	114.7	80	33.19	123.27	1.58	158.04	Vapor	184.30	841,764
3-PN	114.7	-272	33.19	123.27	1.58	158.04	Vapor	95.82	437,624
4-PN	114.7	-272	33.19	123.27	1.58	158.04	Liq&Vap	89.14	407,123
5-PN	114.7	-272	4.86	19.99	0.23	25.08	Vapor	95.82	69,451
6-PN	52.2	-282.5	4.86	19.99	0.23	25.08	Vapor	55.82	69,451
7-PN	114.7	-272	23.05	94.38	1.10	118.53	Vapor	95.82	328,268
8-PN	112.0	-240	23.05	94.38	1.10	118.53	Vapor	104.56	358,183
10-PN	21.0	-307	23.05	94.38	1.10	118.53	Vapor	90.80	311,070
11-PN	21.0	-306	33.16	117.38	1.55	152.09	Vapor	90.96	399,804
12-PN	19.0	-280	33.16	117.38	1.55	152.09	Vapor	97.90	430,305
13-PN	14.7	72	33.16	117.38	1.55	152.09	Vapor	183.04	804,530
14-PN	114.7	-275.6	5.27	8.91	0.25	14.43	Liquid	22.55	9,404
15-PN	21.0	-304.3	5.27	8.91	0.25	14.43	Liq&Vap	22.55	9,404
27	21.0	-304.3	5.27	8.91	0.25	14.43	Liq&Vap	34.75	14,492
16-PN	52.2	-291.9	4.83	14.10	0.20	19.13	Liquid	12.77	7,060
17-PN	21.0	-304.3	4.83	14.10	0.20	19.13	Liq&Vap	12.77	7,060
18-PN	21.0	-304.3	10.10	23.01	0.45	33.56	Vapor	91.49	88,734
20-PN	114.7	-298	0.03	5.89	0.03	5.95	Liquid	12.02	2,060
29	114.7	-298	0.03	5.89	0.03	5.95	Liquid	12.02	2,060
30	4014.7	-298	0.03	5.89	0.03	5.95	Vapor	12.02	2,060

NOTE: 3% Reversal Loss not included in Point 1 Tabulation

## Overall Heat Balance

### Gaseous Oxygen Production




Figure 10 Gaseous Oxygen Heat Balance

Enthalpy of the Liquid O<sub>2</sub> Pumped, H<sub>O</sub>

At the condition of 4014.7 PSIA the enthalpy of the pumped liquid is

$$H_O = 8.89 \text{ Btu/Lb}$$

For x Lbs. pumped

$$H_O = 8.89x \text{ Btu}$$

Enthalpy of the Effluent Waste Air, H<sub>W</sub>

At the conditions of 72°F and 1 PSIG the enthalpy of the effluent waste air equals the sum of the enthalpies of the constituents.

The enthalpy of nitrogen under these conditions is

$$H_{NW} = 183.5 \text{ Btu/Lb}$$

All of the nitrogen contained in the intake air will be waste thus

$$H_{NW} = 183.5 \times 79 = 14,497 \text{ Btu}$$

The enthalpy of oxygen under these conditions is

$$H_{OW} = 181.2 \text{ Btu/Lb}$$

The oxygen contained in the waste air will be

$(21 - x)$  Lbs/100 Lbs of Air Feed hence

$$H_{O_2} = 181.2 (21 - x)$$

$$= 3,805 - 181.2x$$

$$H_W = H_{NW} + H_{O_2} = 14,497 + 3,805 - 181.2x$$

$$H_W = 18,302 - 181.2x \text{ Btu}$$

#### Total Heat Balance

The total heat balance will be

$$H_A + H.L. + H_p = H_W + R + H_0$$

$$18,430 + 150 + 30.53x = 18,302 - 181.2x + 1,018 + 8.89x$$

$$740 = 203.74x$$

$$x = 3.63 \text{ Lbs } O_2/100 \text{ Lbs Air Feed or a } 3.63\% \text{ by weight recovery}$$

The required air intake for two tons per day will be

$$Q = 2 \frac{\text{Tons}}{\text{Day}} \times \frac{2000 \text{ Lbs}}{1 \text{ Ton}} \times \frac{1 \text{ Days}}{24 \text{ Hr}} \times \frac{1 \text{ Hrs}}{60 \text{ Min}} \times \frac{1 \text{ Cu Ft}}{0.075 \text{ Lb}} \times \frac{1}{0.0363}$$

$$= 1020 \text{ SCFM}$$

Assuming 3% Loss upon Reversal

$$Q = 1050 \text{ SCFM}$$

Summary: Gaseous Oxygen Production

As in the liquid nitrogen cycle the following points are the result of the thermodynamic analysis:

Pt. No	Pressure (PSIA)	Temp. (°F)	Composition (Lb Mols/Hr)				Phase	Enthalpy Btu/Lb	Total Heat, Btu/Hr
			O <sub>2</sub>	N <sub>2</sub>	A	Total			
*1-PO	14.7	70	33.35	123.88	1.59	158.82	Vapor	182.74	838,758
2-PO	114.7	80	33.35	123.88	1.59	158.82	Vapor	184.30	845,918
3-PO	114.7	-272	33.35	123.88	1.59	158.82	Vapor	95.79	439,666
4-PO	114.7	-272	33.35	123.88	1.59	158.82	Liq&Vap	88.11	404,433
5-PO	114.7	-272	4.43	18.40	0.21	23.04	Vapor	95.79	63,782
22-PO	89	-276	4.43	18.40	0.21	23.04	Vapor	95.79	63,782
7-PO	114.7	-272	22.89	95.14	1.09	119.12	Vapor	95.79	329,764
8-PO	112	-240	22.89	95.14	1.09	119.12	Vapor	104.50	359,748
10-PO	21	-306	22.89	95.14	1.09	119.12	Vapor	90.93	313,033
11-PO	21	-305	28.17	123.88	1.56	153.61	Vapor	90.02	398,193
12-PO	21	-281	28.17	123.88	1.56	153.61	Vapor	97.98	433,426
13-PO	14.7	72	28.17	123.88	1.56	153.61	Vapor	182.97	809,694
14-PO	114.7	-275.6	6.03	10.34	0.29	16.66	Liquid	22.55	10,887
15-PO	21	-304.3	6.03	10.34	0.29	16.66	Liq&Vap	22.55	10,887
28	21	-304.3	6.03	10.34	0.29	16.66	Liq&Vap	33.11	15,942
23-PO	89	-282	4.43	18.40	0.21	23.04	Liquid	19.18	12,771
24-PO	21	-304.3	4.43	18.40	0.21	23.04	Liq&Vap	19.18	12,771
25-PO	21	-311.5	5.28	28.74	0.47	34.49	Vapor	87.71	84,703
19-PO	21	-305	5.28	28.74	0.47	34.49	Vapor	88.14	85,127
26-PO	21	-291	5.18	0.00	0.03	5.21	Liquid	11.43	1,906
31	21	-298	5.18	0.00	0.03	5.21	Liquid	8.89	1,482
32	4014.7	-298	5.18	0.00	0.03	5.21	Vapor	8.89	1,482

NOTE: 3% Reversal Loss not included in Point 1 Tabulation

## SECTION IV

### EQUIPMENT SPECIFICATIONS

#### General

The equipment specifications listed below are considered to meet the requirements of the liquid oxygen, nitrogen generator from the viewpoints of performance, size, and weight. However, they shall be subject to possible changes resulting from final design considerations as well as availability of materials. The layout of the equipment components within a semitrailer is illustrated in Figure 12.

#### SEMITRAILER

#### Description

Semitrailer - The semitrailer shall be a Fruehauf semitrailer. It shall be constructed so that it is adaptable for towing by a standard Army truck tractor, and shall withstand the strains of service encountered when towed across the country with full equipment. The unit shall not exceed the following dimensions:

Height: 12 ft. 0 in.  
Width: 9 ft. 6 in.  
Length: 32 ft. 0 in.

The total weight of the semitrailer and equipment shall be approximately 45,756 pounds, of which approximately 16,450 pounds shall represent the weight of the semitrailer. The semitrailer shall permit a clear sweep of 70 inches behind the king pin for full turning. A standard SAE king pin shall be provided and shall be located approximately 22 inches back of the trailer front edge to permit the swinging of the trailer corner through a clear space of 62 inches. The trailer fifth wheel plate shall be of sufficient size to fit a 36-inch diameter fifth wheel on the truck tractor and shall be 53 inches from a level ground surface when the trailer floor is level.



#### Running Gear

Wheels - The wheels, studs and cap nuts shall conform to applicable Government specifications.


Wheel Hubs - The wheel hubs shall be fitted with tapered roller bearings of adequate size for the required speeds and loads. Bearings shall conform to SAE standards.

Tires - Tires shall be of the heavy duty, truck-and-bus, balloon type, with nondirectional mud-and-snow type tread.

Tubes - Tubes shall be of the heavy duty type.




PLAN




PLAN VIEW OF TRAILER TWO-FLOOR.

35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68																																



~ PLAN VIEW OF TRAILER SUB-FLANGE

Q138	Q139	Q140	Q141	Q142	Q143	Q144	Q145	Q146	Q147	Q148	Q149	Q150	Q151	Q152	Q153	Q154	Q155	Q156	Q157	Q158	Q159	Q160	Q161	Q162	Q163	Q164	Q165	Q166	Q167	Q168	Q169	Q170	Q171	Q172	Q173	Q174	Q175	Q176	Q177	Q178	Q179	Q180	Q181	Q182	Q183	Q184	Q185	Q186	Q187	Q188	Q189	Q190	Q191	Q192	Q193	Q194	Q195	Q196	Q197	Q198	Q199	Q200	Q201	Q202	Q203	Q204	Q205	Q206	Q207	Q208	Q209	Q210	Q211	Q212	Q213	Q214	Q215	Q216	Q217	Q218	Q219	Q220	Q221	Q222	Q223	Q224	Q225	Q226	Q227	Q228	Q229	Q230	Q231	Q232	Q233	Q234	Q235	Q236	Q237	Q238	Q239	Q240	Q241	Q242	Q243	Q244	Q245	Q246	Q247	Q248	Q249	Q250	Q251	Q252	Q253	Q254	Q255	Q256	Q257	Q258	Q259	Q260	Q261	Q262	Q263	Q264	Q265	Q266	Q267	Q268	Q269	Q270	Q271	Q272	Q273	Q274	Q275	Q276	Q277	Q278	Q279	Q280	Q281	Q282	Q283	Q284	Q285	Q286	Q287	Q288	Q289	Q290	Q291	Q292	Q293	Q294	Q295	Q296	Q297	Q298	Q299	Q300	Q301	Q302	Q303	Q304	Q305	Q306	Q307	Q308	Q309	Q310	Q311	Q312	Q313	Q314	Q315	Q316	Q317	Q318	Q319	Q320	Q321	Q322	Q323	Q324	Q325	Q326	Q327	Q328	Q329	Q330	Q331	Q332	Q333	Q334	Q335	Q336	Q337	Q338	Q339	Q340	Q341	Q342	Q343	Q344	Q345	Q346	Q347	Q348	Q349	Q350	Q351	Q352	Q353	Q354	Q355	Q356	Q357	Q358	Q359	Q360	Q361	Q362	Q363	Q364	Q365	Q366	Q367	Q368	Q369	Q370	Q371	Q372	Q373	Q374	Q375	Q376	Q377	Q378	Q379	Q380	Q381	Q382	Q383	Q384	Q385	Q386	Q387	Q388	Q389	Q390	Q391	Q392	Q393	Q394	Q395	Q396	Q397	Q398	Q399	Q400	Q401	Q402	Q403	Q404	Q405	Q406	Q407	Q408	Q409	Q410	Q411	Q412	Q413	Q414	Q415	Q416	Q417	Q418	Q419	Q420	Q421	Q422	Q423	Q424	Q425	Q426	Q427	Q428	Q429	Q430	Q431	Q432	Q433	Q434	Q435	Q436	Q437	Q438	Q439	Q440	Q441	Q442	Q443	Q444	Q445	Q446	Q447	Q448	Q449	Q450	Q451	Q452	Q453	Q454	Q455	Q456	Q457	Q458	Q459	Q460	Q461	Q462	Q463	Q464	Q465	Q466	Q467	Q468	Q469	Q470	Q471	Q472	Q473	Q474	Q475	Q476	Q477	Q478	Q479	Q480	Q481	Q482	Q483	Q484	Q485	Q486	Q487	Q488	Q489	Q490	Q491	Q492	Q493	Q494	Q495	Q496	Q497	Q498	Q499	Q500	Q501	Q502	Q503	Q504	Q505	Q506	Q507	Q508	Q509	Q510	Q511	Q512	Q513	Q514	Q515	Q516	Q517	Q518	Q519	Q520	Q521	Q522	Q523	Q524	Q525	Q526	Q527	Q528	Q529	Q530	Q531	Q532	Q533	Q534	Q535	Q536	Q537	Q538	Q539	Q540	Q541	Q542	Q543	Q544	Q545	Q546	Q547	Q548	Q549	Q550	Q551	Q552	Q553	Q554	Q555	Q556	Q557	Q558	Q559	Q560	Q561	Q562	Q563	Q564	Q565	Q566	Q567	Q568	Q569	Q570	Q571	Q572	Q573	Q574	Q575	Q576	Q577	Q578	Q579	Q580	Q581	Q582	Q583	Q584	Q585	Q586	Q587	Q588	Q589	Q590	Q591	Q592	Q593	Q594	Q595	Q596	Q597	Q598	Q599	Q600	Q601	Q602	Q603	Q604	Q605	Q606	Q607	Q608	Q609	Q610	Q611	Q612	Q613	Q614	Q615	Q616	Q617	Q618	Q619	Q620	Q621	Q622	Q623	Q624	Q625	Q626	Q627	Q628	Q629	Q630	Q631	Q632	Q633	Q634	Q635	Q636	Q637	Q638	Q639	Q640	Q641	Q642	Q643	Q644	Q645	Q646	Q647	Q648	Q649	Q650	Q651	Q652	Q653	Q654	Q655	Q656	Q657	Q658	Q659	Q660	Q661	Q662	Q663	Q664	Q665	Q666	Q667	Q668	Q669	Q670	Q671	Q672	Q673	Q674	Q675	Q676	Q677	Q678	Q679	Q680	Q681	Q682	Q683	Q684	Q685	Q686	Q687	Q688	Q689	Q690	Q691	Q692	Q693	Q694	Q695	Q696	Q697	Q698	Q699	Q700	Q701	Q702	Q703	Q704	Q705	Q706	Q707	Q708	Q709	Q710	Q711	Q712	Q713	Q714	Q715	Q716	Q717	Q718	Q719	Q720	Q721	Q722	Q723	Q724	Q725	Q726	Q727	Q728	Q729	Q730	Q731	Q732	Q733	Q734	Q735	Q736	Q737	Q738	Q739	Q740	Q741	Q742	Q743	Q744	Q745	Q746	Q747	Q748	Q749	Q750	Q751	Q752	Q753	Q754	Q755	Q756	Q757	Q758	Q759	Q760	Q761	Q762	Q763	Q764	Q765	Q766	Q767	Q768	Q769	Q770	Q771	Q772	Q773	Q774	Q775	Q776	Q777	Q778	Q779	Q780	Q781	Q782	Q783	Q784	Q785	Q786	Q787	Q788	Q789	Q790	Q791	Q792	Q793	Q794	Q795	Q796	Q797	Q798	Q799	Q800	Q801	Q802	Q803	Q804	Q805	Q806	Q807	Q808	Q809	Q810	Q811	Q812	Q813	Q814	Q815	Q816	Q817	Q818	Q819	Q820	Q821	Q822	Q823	Q824	Q825	Q826	Q827	Q828	Q829	Q830	Q831	Q832	Q833	Q834	Q835	Q836	Q837	Q838	Q839	Q840	Q841	Q842	Q843	Q844	Q845	Q846	Q847	Q848	Q849	Q850	Q851	Q852	Q853	Q854	Q855	Q856	Q857	Q858	Q859	Q860	Q861	Q862	Q863	Q864	Q865	Q866	Q867	Q868	Q869	Q870	Q871	Q872	Q873	Q874	Q875	Q876	Q877	Q878	Q879	Q880	Q881	Q882	Q883	Q884	Q885	Q886	Q887	Q888	Q889	Q890	Q891	Q892	Q893	Q894	Q895	Q896	Q897	Q898	Q899	Q900	Q901	Q902	Q903	Q904	Q905	Q906	Q907	Q908	Q909	Q910	Q911	Q912	Q913	Q914	Q915	Q916	Q917	Q918	Q919	Q920	Q921	Q922	Q923	Q924	Q925	Q926	Q927	Q928	Q929	Q930	Q931	Q932	Q933	Q934	Q935	Q936	Q937	Q938	Q939	Q940	Q941	Q942	Q943	Q944	Q945	Q946	Q947	Q948	Q949	Q950	Q951	Q952	Q953	Q954	Q955	Q956	Q957	Q958	Q959	Q960	Q961	Q962	Q963	Q964	Q965	Q966	Q967	Q968	Q969	Q970	Q971	Q972	Q973	Q974	Q975	Q976	Q977	Q978	Q979	Q980	Q981	Q982	Q983	Q984	Q985	Q986	Q987	Q988	Q989	Q990	Q991	Q992	Q993	Q994	Q995	Q996	Q997	Q998	Q999	1000
Q138	Q139	Q140	Q141	Q142	Q143	Q144	Q145	Q146	Q147	Q148	Q149	Q150	Q151	Q152	Q153	Q154	Q155	Q156	Q157	Q158	Q159	Q160	Q161	Q162	Q163	Q164	Q165	Q166	Q167	Q168	Q169	Q170	Q171	Q172	Q173	Q174	Q175	Q176	Q177	Q178	Q179	Q180	Q181	Q182	Q183	Q184	Q185	Q186	Q187	Q188	Q189	Q190	Q191	Q192	Q193	Q194	Q195	Q196	Q197	Q198	Q199	Q200	Q201	Q202	Q203	Q204	Q205	Q206	Q207	Q208	Q209	Q210	Q211	Q212	Q213	Q214	Q215	Q216	Q217	Q218	Q219	Q220	Q221	Q222	Q223	Q224	Q225	Q226	Q227	Q228	Q229	Q230	Q231	Q232	Q233	Q234	Q235	Q236	Q237	Q238	Q239	Q240	Q241	Q242	Q243	Q244	Q245	Q246	Q247	Q248	Q249	Q250	Q251	Q252	Q253	Q254	Q255	Q256	Q257	Q258	Q259	Q260	Q261	Q262	Q263	Q264	Q265	Q266	Q267	Q268	Q269	Q270	Q271	Q272	Q273	Q274	Q275	Q276	Q277	Q278	Q279	Q280	Q281	Q282	Q283	Q284	Q285	Q286	Q287	Q288	Q289	Q290	Q291	Q292	Q293	Q294	Q295	Q296	Q297	Q298	Q299	Q300	Q301	Q302	Q303	Q304	Q305	Q306	Q307	Q308	Q309	Q310	Q311	Q312	Q313	Q314	Q315	Q316	Q317	Q318	Q319	Q320	Q321	Q322	Q323	Q324	Q325	Q326	Q327	Q328	Q329	Q330	Q331	Q332	Q333	Q334	Q335	Q336	Q337	Q338	Q339	Q340	Q341	Q342	Q343	Q344	Q345	Q346	Q347	Q348	Q349	Q350	Q351	Q352	Q353	Q354	Q355	Q356	Q357	Q358	Q359	Q360	Q361	Q362	Q363	Q364	Q365	Q366	Q367	Q368	Q369	Q370	Q371	Q372	Q373	Q374	Q375	Q376	Q377	Q378	Q379	Q380	Q381	Q382	Q383	Q384	Q385	Q386	Q387	Q388	Q389	Q390	Q391	Q392	Q393	Q394	Q395	Q396	Q397	Q398	Q399	Q400	Q401	Q402	Q403	Q404	Q405	Q406	Q407	Q408	Q409	Q410	Q411	Q412	Q413	Q414	Q415	Q416	Q417	Q418	Q419	Q420	Q421	Q422	Q423	Q424	Q425	Q426	Q427	Q428	Q429	Q430	Q431	Q432	Q433	Q434	Q435	Q436	Q437	Q438	Q439	Q440	Q441	Q442	Q443	Q444	Q445	Q446	Q447	Q448	Q449	Q450	Q451	Q452	Q453	Q454	Q455	Q456	Q457	Q458	Q459	Q460	Q461	Q462	Q463	Q464	Q465	Q466	Q467	Q468	Q469	Q470	Q471	Q472	Q473	Q474	Q475	Q476	Q477	Q478	Q479	Q480	Q481	Q482	Q483	Q484	Q485	Q486	Q487	Q488	Q489	Q490	Q491	Q492	Q493	Q494	Q495	Q496	Q497	Q498	Q499	Q500	Q501	Q502	Q503	Q504	Q505	Q506	Q507	Q508	Q509	Q510	Q511	Q512	Q513	Q514	Q515	Q516	Q517	Q518	Q519	Q520	Q521	Q522	Q523	Q524	Q525	Q526	Q527	Q528	Q529	Q530	Q531	Q532	Q533	Q534	Q535	Q536	Q537	Q538	Q539	Q540	Q541	Q542	Q543	Q544	Q545	Q546	Q547	Q548	Q549	Q550	Q551	Q552	Q553	Q554	Q555	Q556	Q557	Q558	Q559	Q560	Q561	Q562	Q563	Q564	Q565	Q566	Q567	Q568	Q569	Q570	Q571	Q572	Q573	Q574	Q575	Q576	Q577	Q578	Q579	Q580	Q581	Q582	Q583	Q584	Q585	Q586	Q587	Q588	Q589	Q590	Q591	Q592	Q593	Q594	Q595	Q596	Q597	Q598	Q599	Q600	Q601	Q602	Q603	Q604	Q605	Q606	Q607	Q608	Q609	Q610	Q611	Q612	Q613	Q614	Q615	Q616	Q617	Q618	Q619	Q620	Q621	Q622	Q623	Q624	Q625	Q626	Q627	Q628	Q629	Q630	Q631	Q632	Q633	Q634	Q635	Q636	Q637	Q638	Q639	Q640	Q641	Q642	Q643	Q644	Q645	Q646	Q647	Q648	Q649																																																																																																																																																																																																																																																																																																																																																															





## Brakes

**Service Brakes** - Service brakes, controllable from the driver's seat of the towing vehicle, shall be provided. The drums shall have flanges or ribbing to prevent objectionable distortion when the brakes are applied. The brakes shall be of the internal expanding, two shoe, heavy-duty type, having constant lift cams and rigid brake-shoe anchors, and shall be operated through fully enclosed worm-gear type slack adjusters. Brakes, anchors, and cam shall have suitable lubrication fittings.

**Service Brake Controls (Air)** - All detail parts and assemblies of the brake control system shall be equal to and interchangeable with the equipment manufactured by The Bendix Westinghouse Automotive Air Brake Company, Elyria, Ohio, and shall be installed in accordance with the manufacturer's latest recommendations. The controls shall be provided with standard emergency break-away features. The break-away arrangement shall conform to requirements of the Interstate Commerce Commission. The controls shall be sealed in a manner that will ensure satisfactory operation in all kinds of weather. All chambers shall be provided with drains on the non-pressure side. Air hose connections and fittings shall be of the replaceable type with spring protectors. Air line filters shall be provided in both emergency and service lines. A relay emergency exhaust check valve and heavy-duty clamping studs shall be furnished. The standard air-brake couplings shall be provided for connecting the brake lines to the towing vehicle. A dummy coupling shall be attached with a chain to each of the air hose couplings. Two detachable air hose lines of proper length and equipped with standard air hose couplings, shall be supplied for connecting the brake system to the towing vehicle. When detached, the hose lines, with electrical connecting cable, shall be carried on the generating plant.

**Parking Brakes** - In addition to the air-brake mechanism, a ratchet-and-pawl type mechanism, or equivalent, shall be provided for operating and setting the brakes by hand. This brake shall be capable of skidding the wheels under full load on a dry, level, concrete pavement. The parking brakes shall be operated by a crank or lever placed in a suitable, protected position on the right hand side or rear of the vehicle. No part of the brake mechanism shall be a factor limiting the travel clearance.

**Landing Gear** - The landing gear shall be of rugged construction, shall be manually operated, and shall be so designed that the wheels may be independently operated to serve as leveling jacks. The landing gear shall be provided with a locking mechanism to lock the landing gear in any position. Two, built-in, screw-type leveling jacks shall be provided at the rear of the trailer. The jacks shall be dirt-proof and self-aligning. Suitable jack planks shall be furnished, conveniently mounted under the trailer.

**Body** - The body shall be of van-type with door and/or window openings designed to afford the most efficient operating conditions. The roof shall be crowned for drainage purposes, and shall be made in removable sections or provided with removable hatches to permit removal and replacement of equipment components within the van. The roofing material shall have sufficient strength to support a 200 pound man walking thereon. Suitable heavy-duty drip moulding shall be provided around the entire roof.

**Floor** - The semitrailer floor shall be adequate for the equipment loads and operating conditions. When an all metal floor is provided, it shall be coated with a suitable non-skid, plastic material. When a wood floor is provided, the wood for the floor shall be either maple or birch, second grade, in accordance with the National Maple Flooring Manufacturer's Association Grading Rules, or oak, select grade, in accordance with the National Oak Flooring Manufacturer's Association Grading Rules. Wood flooring shall be not less than  $1\frac{1}{2}$  inches thick and shall be surfaced two sides and tongue-and-grooved. Floors shall be chemically treated to repel insects. Flooring shall run lengthwise of the trailer and shall be securely fastened to each cross member by means of galvanized wood screws with heads countersunk to be flush with the floor. The floor shall be sealed at all joints with pitch or other suitable sealing compound.

**Doors and/or Windows** - Doors, removable panels or hatches shall be provided on the semitrailer as required for convenience of operation, accessibility of plant components, and to facilitate removal of equipment for repair and maintenance. Windows shall be installed in the van-type body of the semitrailer as required. Windows shall be glazed with shatterproof glass.

**Steps** - Demountable-type steps shall be provided for use at the doors. Steps shall be provided with suitable grab handles and non-slip tread plates, and shall be easily attached and detached at the sill. Provision shall be made for stowing steps inside the semitrailer when not in use.

**Wiring** - The vehicle shall be wired for an electrical supply of 24 volts direct current. Cable used for wiring shall be encased in flexible non-metallic tubing. Terminal lugs shall be soldered to the wire ends. Junction blocks shall have bases made of thermosetting, laminated, phenol-formaldehyde plastic, or other equally suitable material, and shall be equipped with suitable studs, washers and nuts for the attachment of terminal lugs. The circuits shall be color or number traced. Suitable grommets, or clamps, to prevent chafing of cable, shall be furnished where wire passes through structural members. A receptacle with hinged cover, to allow the running lights of the semitrailer to be controlled from the driver's seat of the towing vehicle, shall be recessed in the frame. A cable to connect the trailer to the towing vehicle shall be provided.

**Lamps and Reflector Assemblies** - All lamps shall be readily accessible for the changing of bulbs and lenses, and for making repairs. The stop and tail lamps shall be recessed approximately  $\frac{1}{2}$  inch from the surface of the frame member. The following lamps and reflectors shall be provided on the vehicle, located to conform to Interstate Commerce Commission Motor Carrier Safety Regulations:

Reflect Reflector (Red and Amber)  
Receptacle and Hinged Cover Assembly  
R.H. Tail Lamp Assembly, 24 Volt  
L.H. Tail Lamp Assembly, 24 Volt  
Clearance Lamp Assembly, 24 Volt

**Semitrailer Insulation** - The semitrailer operating space shall be insulated with suitable insulating material such as mineral fiber bonded together with a thermosetting plastic resin to form a resilient, semi-rigid, dimensionally stable insulation, sealed in place against moisture infiltration.

**Electrical Equipment** - A suitable number of dome lights with necessary wiring and switches, and with bulbs of sufficient candlepower shall be installed to provide adequate light for operating the equipment at night. A sufficient number of convenience outlets shall be provided for emergency drop-light cords. An emergency auxiliary lighting system supplied by power from the 24 volt diesel engine starting battery bank shall be provided.

**Construction Design Methods** - All construction design methods and materials for all parts of the unit shall be selected for the lightest possible end item without sacrifice of dependability and strength.

**Lubrication** - All moving parts shall be provided with suitable means of lubrication.

**Lubricants** - All moving parts shall be designed to operate efficiently and satisfactorily when lubricated with standard Armed Forces lubricants.

**Grease Fittings** - Grease fittings shall be located in accessible, protected positions. A bright red circle shall be painted around each lubricating point.

**Caution Plates** - Where the use of high-pressure lubricating equipment, 1,000 PSI or higher, will damage grease seals or other parts, a suitable warning shall be affixed to the equipment in a conspicuous location.

**Fungus Control** - The semitrailer shall be treated to resist the growth of fungus.

**Lifting Attachments** - The semitrailer shall be provided with suitable lifting attachments to enable the trailer, with all equipment installed in it, to be lifted in its normal position. The lifting attachment shall have a minimum safety factor of five based on the ultimate strength of the material. The eye of each lifting attachment shall be not less than three inches in diameter.

**Manufacturer's Identification** - The semitrailer shall bear the manufacturer's name and/or trademark on a name plate securely affixed in a conspicuous place. In lieu of the name plate, the manufacturer's identification may be cast integral with, stamped, or otherwise permanently marked upon the components of the equipment.

**Instruction Plates** - The semitrailer, when applicable, shall be equipped with instruction plates, suitably located, describing any special or important procedures to be followed in operating and servicing the equipment.

**Treatment, Painting, and Stenciling** - All parts of the semitrailer body and running gear shall be treated and painted to resist the effects of sand, dust, humidity and moist salt air.

**Stenciling** - The gross weight of the semitrailer with all equipment installed in it shall be stenciled on each side of the semitrailer in such manner as to be readily discernible to military personnel. The prescribed tire pressure shall be stenciled on the frame or body of the unit in a position near the wheels, using block- or stencil-type letters not more than one inch high.

## AIR FILTER

### Description

The air filter element shall be a Dollinger Corporation staynew Model WKE-4, dry panel type air filter, complete with cell frame and insert. The filtering medium shall be bonded glass. Two elements shall be required. They shall be mounted in a lightweight steel duct.

### Specifications

Nominal Filter Element	
Size, Ins.	
Height	20
Width	25
Thickness	4
Normal Capacity	
Air Volume, CFM	750
Air Velocity, FPM	30
Maximum Capacity	
Air Volume, CFM	1000
Air Velocity, FPM	40
Active Filtering Area, Sq. Ft.	25
Pressure Drop	
At 750 CFM air Volume, Ins. of Water	0.02
At 1000 CFM Air Volume, Ins. of Water	0.04
Duct Size	
Height, Ins.	20
Width, Ins.	14
Length, Ins.	42
Approximate Total Weight, Lbs.	125

## AIR COMPRESSOR

### Description

The air compressor shall consist of three Read Standard Corporation "Standardaire" blowers. Each blower shall be a three lobe, rotary, positive displacement, axial flow, horizontal, heavy duty blower having helical rotors. By compounding one Model 8B14, one Model 7B10 and one Model 5B10 blower, 1000 standard cubic feet per minute of air shall be compressed from intake conditions of 14.7 PSIA and 70°F and discharged as oil-free air at 114.7 PSIA. Each blower shall be equipped with a shaft extension to provide a drive for an inter-cooler or aftercooler fan. This extension shall be capable of transmitting a load of 10 horsepower to the cooling fan by either a direct drive or through the use of a V-belt drive.

Each stage shall be tested individually in accordance with the American Society of Mechanical Engineers Power Test Code (PTC 9-39). Each stage shall be guaranteed to be within the permissible limit of 3% of the specifications listed below.

### Specifications

	<u>1st Stage</u>	<u>2nd Stage</u>	<u>3rd Stage</u>
Blower Model	8B14	7B10	5B10
Speed, RPM	2330	2390	3220
Intake Pressure, PSIA	14.56	30.4	59.9
Discharge Pressure, PSIA	31.4	60.9	115.7
Absolute Pressure Ratio	2.16:1	2.0:1	1.93:1
Intake Volume, CFM	1100	556	277
Intake Temperature, °Rankine	530	560	560
Discharge Temperature, °F	264	302	287
Adiabatic Horsepower	60	56.5	52.3
Brake Horsepower	102	103	99
Overall Adiabatic Efficiency, %	59	55	53
Direction of Rotation, Viewing Driveshaft End	Clockwise	Clockwise	Clockwise
Approximate Size			
Length, In.	45-3/8	41	41
Width, In.	26-5/8	24-5/8	20-1/2
Height, In.	24-3/4	22-1/2	17-1/4
Approximate Weight, Lbs.	1227	950	710

### INTERCOOLERS AND AFTERCOOLER

#### Description

The intercoolers and aftercooler shall be Trane Company coolers. They shall be of all aluminum construction. The cooling air face shall measure 20-5/8 inches by 32 inches, and the cooling air flow length shall be 10 inches.

#### Specifications

	<u>1st Stage</u>	<u>2nd Stage</u>	<u>3rd Stage</u>
	<u>Cooler</u>	<u>Cooler</u>	<u>Cooler</u>
Duty, Btu/Hr	235,000	270,000	235,000
Hot Air Side			
Flow, Lbs/Hr	4,500	4,500	4,500
Inlet Temperature, °F	264	302	287
Outlet Temperature, °F	90	90	90
Inlet Pressure, PSIG	16.7	46.7	101.0
Pressure Drop, PSI	0.49	0.30	0.22
HL, Btu/Hr, Sq.Ft., of	27.8	27.8	27.8
Number of Passages	24	24	24
Flow Length, In.	32	32	32
Fin Type	1/8 In. Serrated	1/8 In. Serrated	1/8 In. Serrated
Fin Height x Thickness, In.	0.375 x 0.006	0.375 x 0.006	0.375 x 0.006

1/ Sensible heat transfer coefficient corrected for fin efficiency.

	<u>1st Stage Cooler</u>	<u>2nd Stage Cooler</u>	<u>3rd Stage Cooler</u>
Fin Spacing, Per In.	12	12	12
Total Surface, Sq. Ft.	541	541	541
Air Inlet Connection Size, In.	6	4	3
Air Outlet Connection Size, In.	6	4	3
Air Blowdown Connection Size, In.	2	1-1/2	1-1/4
<b>Cooling Air Side</b>			
Flow, Lbs/Hr	13,500	13,500	13,500
Inlet Temperature, °F	80	80	80
Outlet Temperature, °F	152.3	163.1	152.3
Pressure Drop, Ins. Water	4.24	4.28	4.24
H, Btu/Hr., Sq. Ft., °F	22.9	22.9	22.9
Number of Passages	25	25	25
Flow Length, Ins.	10	10	10
Fin Type	Herringbone	Herringbone	Herringbone
Fin Height x Thickness, Ins.	0.416 x 0.006	0.416 x 0.006	0.416 x 0.006
Fin Spacing, Per In.	17	17	17
Total Surface, Sq. Ft.	850	850	850
Approximate Total Weight, Lbs.	120	120	120

#### INTER- AND AFTERCOOLER FANS

##### Description

The inter- and aftercooler fans shall be Trane Company centrifugal fans with the blades inclined backward to the direction of rotation. They shall be of single width and shall have single inlets. They shall be of lockseam-type construction, with convertible discharge orientation, and with standard steel shafts.

##### Specifications

	<u>1st Stage</u>	<u>2nd Stage</u>	<u>3rd Stage</u>
Fan Model	16 BI SWSI	16 BI SWSI	13 BI SWSI
Fan Size	16	16	13
Fan Arrangement	2	2	2
Fan Class	II	II	II
Wheel Width, %	85	80	95
Fan Speed, RPM	2350	2390	3220
Direction of Rotation Viewing Driveshaft End	Clockwise	Clockwise	Clockwise
Delivery, CFM	3465	3525	3465
Static Pressure, Ins. of Water	4.24	4.28	4.24
Brake Horsepower	3.28	3.42	3.69
Orientation of Discharge	Up Blast	Up Blast	Up Blast
Approximate Size			
Length, In.	28-3/4	28-3/4	26-1/8
Width, In.	31-3/4	31-3/4	26
Height, In.	33-3/8	33-3/8	27-5/8
Approximate Weight, Lbs.	86	86	70

## DIESEL ENGINE

### Diesel Engine Horsepower Requirements

In this generator, the blowers and inter- and aftercooler fans of each stage are direct-driven in tandem by separate diesel engines through suitable transmissions. In addition, a 18.7 Kva, 120/208 volt, 3 phase, 60 cycle electrical generator is belt driven by the third-stage diesel engine. The following table is a compilation of the anticipated brake horsepower loads on the individual diesel engines required to drive these components:

Stage	Brake Horsepower				Total
	Blower	Transmission Loss - 2 to 4%	Intercooler Fan	Electric Generator	
1st Stage	102	3.57	3.28		108.85
2nd Stage	103	3.60	3.42		110.02
3rd Stage	99	3.46	3.69	11.0	117.15

### Description

The three diesel engines shall be General Motors Corporation two cycle, six cylinder, radiator-cooled, short base, open diesel engines, Series 6-71, Model 6030C.

### Specifications

Engine Model Number	6030C
Engine	GM 6-71 PC55
	2-Cycle Diesel
Number of Cylinders	6
Bore, In.	4-1/4
Stroke, In.	5
Total Displacement, Cu. In.	425.6
Rated BHP, Basic Engine at 200 RPM	200
Rated BHP, with Standard Equipment at 1800 RPM	153
Continuous BHP, with Standard Equipment at 1800 RPM	138
Continuous BHP, with Standard Equipment at 1600 RPM	130
BMEP, Continuous Rating at 1800 RPM, PSI	71
BMEP, Continuous Rating at 1600 RPM, PSI	75
Maximum Torque, 1000 RPM (60 Cu. MM. Injector), Lb Ft	526
Piston Speed at 1800 RPM, FPM	1500
Piston Speed at 1600 RPM, FPM	1333
Compression Ratio	16:1
Lubrication	Forced Feed
Flywheel Housing Size	No. 1 SAE
Maximum Fuel Pump Lift to Fuel Pump Level, In.	48
Heat Absorbed by Cooling Water (Per HP at Ambient Temperature of 110°F) Btu/HP/Min.	35
Air Required for Scavenging and Combustion at 1800 RPM, CFM	600
Exhaust Back Pressure (Maximum at Manifold Flange at 1800 RPM), In. Hg.	4
Lubricating Oil Refill Capacity, Including Filter(s), Qt.	29
Cooling Water System Capacity, Gal.	8-3/4

Approximate Size

Length, In.

62-13/16

Width, In.

32

Height, In.

49-1/8

Approximate Weight, Dry, Lbs.

2600

Standard Equipment

Rotation - Counterclockwise, viewing flywheel end.

Cooling System - heavy duty radiator, lubricating oil cooler, water outlet manifold, thermostat for temperature control, engine water circulating pump, suction type fan.

Fuel System - Primary and secondary fuel filters, 60 cu. mm. injectors, fuel circulating pump.

Lubrication System - Lubricating oil pressure pump, oil filter assembly.

Instruments - Instrument Panel Assembly includes: Starter switch, ammeter, lube oil pressure gauge, water temperature gauge, throttle control knob, remote control lever and space for accessory air heater controls and tachometer.

Miscellaneous - Fabricated steel base, hydraulic type governor with control on instrument panel, exhaust manifold and companion flange, tools for ordinary maintenance, manual for minor maintenance and operating instructions.

Optional Equipment

Electrical - Battery charging generator and voltage regulator assembly (24 volt, 600 watt insulated) starting motor (24 volt, insulated).

Miscellaneous - Air inlet housing for remotely mounted extra capacity air cleaner, Donaldson extra heavy duty oil bath type air cleaner.

Accessories

Automatic Bell Alarm for high water temperature and low oil pressure, air heater and pump for cold weather starting, 18-inch flexible exhaust connection with pipe thread ends, unmounted muffler for moderate silencing.

DIESEL ENGINE TRANSMISSION

Description

The diesel engine transmission shall be a Cotta Transmission Company Model FA4U-R Transmission equipped with an SAE No. 1 bell housing and Rockford single plate, 14", over-center clutch. It shall be complete with pilot bearings and oil circulating pump. The transmission shall be so designed and constructed, that it is capable of attachment and connection to a General Motors Model 60300 Series 6-71 RC55 Diesel Engine without modification. The transmission bell

housing shall be fabricated with a clutch operating shaft extending through and to the outside on both right and left hand sides of the ball housing to provide for optional location of a clutch operating lever.

#### Specifications

	<u>Unit No. 1</u> <u>1st Stage</u>	<u>Unit No. 2</u> <u>2nd Stage</u>	<u>Unit No. 3</u> <u>3rd Stage</u>
Horsepower to be Transmitted, Minimum	100	100	100
Input Speed, RPM (Approximate)	1580	1620	1600
Output Speed, RPM (Approximate)	2330	2390	3220
Overspeed Ratio	1.476:1	1.476:1	2.012
Transmission Efficiency, Per Cent	96 to 98	96 to 98	96 to 98
Type of Duty	Continuous	Continuous	Continuous
Direction of Rotation, Viewing Output Shaft	Counter- Clockwise	Counter- Clockwise	Counter- Clockwise
Approximate Size			
Length, In.	34	34	34
Width, In.	22	22	22
Height, In.	24	24	24
Approximate Weight, Lbs.	630	630	630

#### DIESEL ENGINE STARTING BATTERY

#### Description

The diesel engine starting battery shall be a Delco Products Division of General Motors Corporation Heavy Duty, Model 25A1, Six-Volt Storage Battery. The battery shall have three lead and acid type cells enclosed in a composition rubber case. Four of these batteries shall be connected in series to generate the 24 volts necessary to start the diesel engines.

#### Specifications

##### Capacity

200 Ampere Hours at 20 Hour Rating  
150 Ampere Hours at 4 Hour Rating

##### Delivery Rates

50 Amperes for 175 Minutes at 80°F  
300 Amperes for 11 Minutes at 0°F  
820 Amperes for 1.5 Minutes at 0°F  
1060 Amperes for 1.5 Minutes at 32°F

At the above rates the battery shall be depleted to an average of one volt per cell.

##### Approximate Size

Length, In. 16-1/2  
Width, In. 7-1/2  
Height, In. 10

Approximate Weight, Lbs. 80

## DIESEL ENGINE FUEL OIL SUPPLY TANK

### Calculation of Size

In accordance with the contract, the fuel supply tank shall have a minimum capacity for 12 hours of continuous operation for the generator at full load.

#### Specific Fuel Consumptions

First-Stage Engine at 108.85 BHP, 1600 RPM	7.14 GPH
Second-Stage Engine at 110.02 BHP, 1600 RPM	7.23 GPH
Third-Stage Engine at 117.15 BHP, 1600 RPM	7.68 GPH

Total	22.05 GPH
-------	-----------

#### Capacity Required

$$V_{\text{req'd}} = 22.05 \frac{(\text{Gal})}{(\text{Hr})} \times 12 (\text{Hrs})$$

$$= 265 \text{ Gals.}$$

$$\text{Use } V_{\text{tank}} = 275 \text{ Gals.}$$

For the trailer which is 9 feet 6 inches wide, a steel, cylindrical fuel tank 8 feet 10 inches long shall be strapped beneath the floor of the air source section.

$$V_{\text{cyl}} = \pi \frac{D_1^2}{4} (\text{cross sectional area}) \times L (\text{length})$$

Also

$$V_{\text{cyl}} = 275 (\text{Gals}) \times 231 \frac{(\text{Cu In})}{(\text{Gal})}$$

$$D_1^2 = \frac{275 \times 231 \times 4}{\pi \times 106}$$

$$D_1 = 27.68 \text{ Ins. Use } 27.75 \text{ Ins.}$$

### Specifications

Inside Diameter, In.	27.75
Length, In.	106.0
Thickness, In.	1/8
Capacity, Gals.	275
Weight, Dry, Lbs.	360
Weight, Wet, Lbs.	2310

## AIR COMPRESSOR CONDENSATE TRAP

### Description

The air compressor condensate trap shall be fabricated by Air Products, Incorporated. It shall have a tangential side inlet and a bottom outlet. It shall have a condensate drain connection at the lowest point in the bottom head.

### Specifications

Material	Steel
Shell Length, Ins.	30
Shell Diameter, Ins.	10
Shell Thickness, Ins.	1/8
Head Diameter, Ins.	10
Head Thickness, Ins.	1/8
Head Height, Ins.	4
Inlet Connection Size, Ins.	4
Outlet Connection Size, Ins.	4
Condensate Drain Connection Size, Ins.	1
Maximum Working Pressure, PSIG	100
Approximate Weight, Lbs.	50

## SWITCH VALVE

### Description

The switch valve shall be manufactured by Air Products, Incorporated. It shall be a double poppet-type valve having a carbon steel body and stainless steel stem. It shall have two 4-inch high pressure air inlet connections; one 5-inch waste air outlet connection; and two 5-inch connections common to both the high pressure air outlet and the waste air inlet. The switch valve shall be actuated by a Logansport Machine Company, Incorporated non-rotating, double-acting air cylinder, Model No. 2106C. The air cylinder shall have a 6-inch bore, 4-inch stroke and 1/2 inch iron pipe size air connections. The air cylinder, in turn, shall be controlled by a Bellows Company four-way solenoid air valve, Model No. EV-15B Electroair Valve, having a 115/8 volt transformer and 1/2 inch iron pipe size air inlet connection. The solenoid valve shall be air powered and shall be actuated in both directions by low-voltage, momentary-energized solenoid coils. It shall have an operating pressure of 50 PSIG, and shall have adjustments provided to limit the speed of the control cylinder in both directions.

## WARM HEAT EXCHANGER

### Description

The warm heat exchanger shall be a Trane Company brazed aluminum core type heat exchanger.

## Specifications

### Core Size

17 in. passage width over channels  
20-7/8 in. no flow (passage stack height)  
88-1/2 in. core length over face channels

### Core Passages

50 passages per core shall be headered into 2 streams of 25 passages each  
16-1/2 in. width inside channels  
0.375 in. nominal passage height

### Fins

Trans 1/8 in. serrated  
0.375 in. nominal height  
15 fins per inch  
0.008 in. thickness  
81 in. effective heat transfer length

### Distribution

Provision shall be made for gas distribution at each end of a passage.

### Headers

The headers shall be fabricated from standard 5 inch 39F aluminum pipe.

### Shell

External parting sheets and 1/4 inch protective pads shall be provided on each core, one on each side of 20-7/8 inch no flow (passage stack height).

### Supports

Support boxes and angles shall be provided at each end of the core.

### Material Thickness, Inches

Outside Core Sheets	-	.064
Parting Sheets	-	.032
Side Channels	-	.040
Top Header Channels	-	.064
Side Protection Fin	-	.008
Packing Fin	-	.008
Distributor Fin	-	.024 Perforated

### Tests

The core shall be subjected to hydrostatic and air pressure tests to check for interpassage and external leakage. The core shall be guaranteed to be satisfactory at a maximum working pressure of 100 PSIG.

## COLD HEAT EXCHANGER

### Description

The cold heat exchanger shall be a Trane Company braced aluminum core type heat exchanger.

### Specifications

#### Core Size

17 in. passage width over channels  
20-7/8 in. no flow (passage stack height)  
80-1/2 in. core length over face channels

#### Core Passages

50 passages per core shall be headered into 3 streams of 20, 20, and 10 passages respectively.  
16-1/2 in. width inside channels  
0.375 in. nominal passage height

#### Fins

Trane 1/8 in. serrated  
0.375 in. nominal height  
15 fins per inch  
0.008 in. thickness  
73 in. effective heat transfer length

#### Distribution

Provision shall be made for gas distribution at each end of a passage.

#### Headers

The headers shall be fabricated from standard 5 inch 3SF aluminum pipe.

#### Shell

External parting sheets and 1/16 inch protective pads shall be provided on each core, one on each side of 20-7/8 inch no flow (passage stack height).

#### Supports

Support boxes and angles shall be provided at each end of the core.

#### Material Thickness, Inches

Outside Core Sheets	-	.064
Parting Sheets	-	.032
Side Channels	-	.040
Top Header Channels	-	.064
Side Protection Fin	-	.008
Packing Fin	-	.008
Distributor Fin	-	.024 Perforated

#### Tests

The core shall be subjected to hydrostatic and air pressure tests to check for interpassage and external leakage. The core shall be guaranteed to be satisfactory at a maximum working pressure of 100 PSIG.

## AIR LIQUEFIER

### Description

The air liquefier shall be a Trane Company braced aluminum core type heat exchanger.

### Specifications

#### Core Size

8-3/4 in. passage width over channels  
12-3/4 in. no flow (passage stack height)  
51-1/4 in. core length over face channels

#### Core Passages

30 passages per core to be headered into 2 streams of 20 and 10 passages.  
16-1/2 in. width inside channels  
0.375 in. nominal passage height

#### Fins

Trane 1/8 in. serrated  
0.375 in. nominal passage height  
15 fins per inch  
0.008 in. thickness  
43-3/4 in. effective heat transfer length

#### Distribution

Provision shall be made for gas distribution at each end of a passage.

#### Headers

The headers shall be fabricated from standard 3 and 5 inch 3SF aluminum pipe.

#### Shells

External parting sheets and 1/4 inch protective pads shall be provided on each core, one on each side of 12-3/4 inch no flow (passage stack height).

#### Supports

Support boxes and angles shall be provided at each end of the core.

#### Material Thicknesses, Inches

Outside Core Sheets	-	.064
Parting Sheets	-	.032
Side Channels	-	.040
Top Header Channels	-	.064
Side Protection Fin	-	.008
Packing Fin	-	.008
Distributor Fin	-	.024 Perforated

#### Tests

The core shall be subjected to hydrostatic and air pressure tests to check for interpassage and external leakage. The core shall be guaranteed satisfactory at a maximum working pressure of 100 PSIG.

## CHECK VALVE

### Description

The check valve shall be manufactured by Air Products, Incorporated. It shall be a double poppet-type valve of stainless steel construction. In one end it shall have one 4-inch high pressure air outlet connection; in the opposite end it shall have one 5-inch waste air inlet connection; and in the side it shall have one 5-inch connection common to both the incoming high pressure air and the effluent waste air. The check valve shall measure approximately 14 inches in length and shall weigh approximately 125 pounds.

## PHASE SEPARATOR

### Description

The phase separator shall be manufactured by Air Products, Incorporated. It shall be provided with a tangential, side, air inlet connection, a top vapor outlet connection, and a bottom liquid outlet connection. In addition, the phase separator shall be provided with connections to accommodate a liquid level gage.

### Specifications

Model	41490D
Material	Copper
Shell Length, Ins.	24
Shell Diameter, Ins.	8-1/8 O.D.
Shell Thickness, Ins.	0.170
Head Diameter, Ins.	8-1/8 I.D.
Head Thickness, Ins.	1/4
Air Inlet Connection Size, Ins.	3-1/8 O.D.
Vapor Outlet Connection Size, Ins.	3-1/8 O.D.
Liquid Outlet Connection Size, Ins.	5/8 O.D.
Upper Liquid Level Gage Connection Size, Ins.	5/8 O.D.
Maximum Working Pressure, PSIG	100
Approximate Overall Length, Ins.	32
Approximate Weight, Lbs.	53

## TURBO EXPANDER

### Description

The turbo expander shall be an Air Products, Incorporated high-speed, centrifugal, expander, equipped with an air loaded energy absorber complete with lubrication system.

### Specifications

The turbo expander shall be designed, built, and guaranteed to operate satisfactorily under the following conditions:

Fluid	Air
Flow Rate, Lb/Min	54.6
Inlet Pressure, PSIA	112
Exhaust Pressure, PSIA	21
Inlet Temperature, °F	-240
Exhaust Temperature, °F	-306
Approximate Weight, Lbs.	160

### EXPANDER LOADER

#### Description

The expander loading device consists of a centrifugal impeller keyed to the expander shaft. The impeller rotates at the same speed as the expander wheel and imparts the shaft energy to the fluid being pumped. The amount of power which is absorbed is proportional to the quantity and density of the pumped fluid. This is controlled by a valve which admits the fluid to the inlet of the loader.

### HYDROCARBON ADSORBER

#### Description

The hydrocarbon adsorber shall be an Air Products, Incorporated, silica gel type adsorber, Model No. 41510D. It shall consist of a pressure vessel having top inlet and bottom outlet connects. The pressure vessel shall be charged with silica gel. It shall be provided with filters to keep foreign particles from entering and silica gel from leaving the adsorber.

### Specifications

#### Pressure Vessel

Material	Copper
Shell Length, Ins.	36
Shell Diameter, Ins.	8-1/8 O.D.
Shell Thickness, Ins.	0.170
Head Diameter, Ins.	8-1/8 I.D.
Head Thickness, Ins.	1/4
Inlet Connection Size, Ins.	5/8 O.D.
Outlet Connection Size, Ins.	5/8 O.D.
Maximum Working Pressure, PSIG	15
Approximate Overall Length, Ins.	46
Approximate Weight, Charged, Lbs.	123

Adsorbent	
Material	Silica Gel
Size, Mesh	3-8
Density, Lbs/Cu. Ft.	38-40
Quantity Required, Lbs.	42
Inlet Filter	
Material	Porex Grade 1
Diameter, Ins.	1-1/8 O.D.
Wall Thickness, Ins.	1/8
Length, Ins.	5-1/4
Primary Outlet Filter	
Material	Alumina Tabular Balls
Ball Diameter, Ins.	1/4
Quantity Required, Cu.Ft.	1/2
Secondary Outlet Filter	
Material	Porex Grade 1
Diameter, Ins.	1-1/8
Wall Thickness, Ins.	1/8
Length, Ins.	5-1/4

#### OXYGEN DISTILLATION COLUMN

##### Description

The distillation column shall be an Air Products, Incorporated column. It shall consist of a tube-type condenser and a low pressure column having a number of bubble-cap pans of conventional design. The high pressure side of the condenser shall be designed and fabricated for a maximum working pressure of 100 PSIG. The low pressure column, which is also the low pressure side of the condenser, shall have a maximum working pressure of 15 PSIG. The column shall be provided with connections, properly sized and located, to accommodate all of the required column feeds and offtakes. Sufficient pans shall be included in the low pressure column to ensure that the product liquid oxygen, when withdrawn from the column at a rate of two tons per day, shall be 99.5% pure when the air available to the oxygen generator is approximately 1000 standard cubic feet per minute, and when the material balances are as calculated in Section III of this report. The column shall be approximately 13 1/8 inches in diameter and 8 feet 6 inches high and shall weigh approximately 600 pounds dry.

#### NITROGEN DISTILLATION COLUMN

##### Description

The distillation column shall be an Air Products, Incorporated column. It shall consist of a tube-type condenser and a high pressure column having a number of bubble-cap pans of conventional design. The high pressure column

and high pressure side of the condenser shall be designed and fabricated for a maximum working pressure of 100 PSIG. The low pressure column and low pressure side of the condenser shall be designed and fabricated for a maximum working pressure of 15 PSIG. The column shall be provided with the necessary connections, properly sized and located to accommodate all of the required column feeds and off-takes. Sufficient pans shall be included in the high pressure column to insure that the product liquid nitrogen when withdrawn from the column at a rate of two tons per day shall be 99.0% pure, when the air available to the generator is approximately 1000 standard cubic feet per minute and when the material balances are as calculated in Section III of this report. The column shall be approximately 13 1/8 inches in diameter and 5 feet 6 inches high and shall weigh approximately 450 pounds dry.

### SUBCOOLER

#### Description

The subcooler shall be an Air Products, Incorporated extended-surface type heat exchanger, Model No. 41506C. In the subcooler, pure liquid shall flow through the tubes of the core while waste air gas shall flow around the tubes through the shell.

#### Specifications

##### Core

Material	Finned Copper Tube
Tube Size, IPS	3/4
Tube Length, Ins.	60
Fin Height, Ins.	1/2
Fin Orientation	Axial
No. of Fins per Circumference	18
No. of Tubes	7
Liquid Inlet Connection Size, Ins.	7/8 O.D.
Liquid Outlet Connection Size, Ins.	7/8 O.D.
Maximum Working Pressure, PSIG	15

##### Shell

Material	Copper
Length, Ins.	75
Diameter, Ins.	6-1/8 O.D.
Thickness, Ins.	0.140
Head Diameter, Ins.	6-1/8 I.D.
Head Thickness, Ins.	0.187
Waste Air Inlet Connection Size, Ins.	3-1/8 O.D.
Waste Air Outlet Connection Size, Ins.	3-1/8 O.D.
Maximum Working Pressure, PSIG	15

Approximate Overall Length, Ins.	91
Approximate Weight, Lbs.	154

## LIQUID PRODUCT PUMPS AND DRIVE MOTORS

### Description

The liquid product pumps shall be an Air Products, Incorporated horizontal, reciprocating-plunger type. The pumps shall be driven through a crank-and-connecting rod mechanism by electric motors through a gear reduction. The pumps shall be provided with thermal breaks which will allow the pump drive mechanisms to operate at atmospheric temperature while the pump cylinders are at the temperature of the liquid product being pumped. The pump capacities shall be controlled by variation of the pump stroke.

### Specifications

#### Pump

Delivery, CFH gas Equivalent	2000
Plunger Diameter, Ins.	5/8
Stroke, Ins.	Variable up to 3
Speed, RPM	100
Intake Pressure, PSIG	7
Discharge Pressure, PSIG	4000

#### Motors

3 Horsepower, 220/440 Volts, 3 Phase, 60 cycle, Squirrel-Cage Induction, Ball Bearing, Horizontal, Open, 40° Rise, Continuous Duty, Normal Torque, Low Starting Current, with 100 RPM American Gear Manufacturers' Association Class III, Helical Gears Hand Matched for Minimum Back Lash and Quiet Operation.

## OXYGEN-NITROGEN VAPORIZER

### Description

The oxygen-nitrogen vaporizer shall be manufactured by Air Products, Incorporated. It shall be a tube-type heat exchanger consisting of copper coils contained within a steel shell. The pure high pressure liquid product shall flow through the copper coils while high pressure air from the after-cooler of the air compressor shall flow across the tubes within the shell.

### Specifications

#### Shell

Material	Steel
Length, Ins.	48
Diameter, Ins.	12
Thickness, Ins.	0.120
Head Diameter, Ins.	12
Head Thickness, Ins.	1/8
Maximum Working Pressure, PSIG	100

Coils	
Material	Copper
Overall Coil Length, Ft.	450
Tube Diameter, Ins.	3/8 O.D.
Wall Thickness, Ins.	0.10
Maximum Working Pressure, PSIG	4000
Approximate Overall Length, Ins.	56
Approximate Weight, Lbs.	270

#### ALTERNATING-CURRENT GENERATOR

##### Specifications

The alternating-current generator shall have the following characteristics: 18.7 Kva, 120/208 volts, 3 phase, 4 wire, 60 cycle, .8 power factor, 1800 RPM, synchronous, horizontal, ball-bearing, drip-proof, self-excited by direct connected exciter, windings of generator and exciter shall be moisture and fungus proof.

The alternating-current generator shall have a shaft extension suitable for a V-belt drive and shall be complete with a solid adjustable base or slide rails.

#### HYDROCARBON ADSORBER REACTIVATION HEATER

##### Description

The hydrocarbon adsorber reactivation heater shall be an Air Products, Incorporated resistance heater, Model No. 31144C. It shall consist of two heating elements, the resistance heating coils of which are imbedded in compacted magnesium oxide which is contained within a grounded, chrome-steel sheath. Each element shall be rated at 1 kilowatt at 230 volts alternating current single phase. The two elements shall be connected in open-delta for the three phase circuit. The maximum allowable sheath temperature shall be 1400 to 1500°F.

#### INTERCONNECTING PIPING

##### Description

The interconnecting piping shall be of as lightweight material as practical. It shall be adequately strong for the service intended and shall be sized to keep pressure losses within tolerable limits. Operating conditions such as temperature, pressure, location and application shall dictate the choice of material to be used. Every piping circuit of the liquid product generator shall be protected against excess pressure by means of pop safety valves.

## AIR SEPARATOR INSTRUMENT PANEL

### Description

The air separator instrument panel shall be fabricated by Air Products, Incorporated. It shall support pressure gages, liquid level gages and temperature indicators which shall serve as operating aids for the liquid oxygen generator. The instrument panel and its supports shall be fabricated of steel. Its measurements shall be approximately 30 inches long by 37 inches wide. The following instruments shall be flush mounted and readily accessible and demountable for service, if necessary.

- High Pressure Column Pressure Gages
- Low Pressure Column Pressure Gages
- High Pressure Product Pressure Gages

- Phase Separator Liquid Level Gage
- High Pressure Column Liquid Level Gages
- Low Pressure Column Liquid Level Gages

- Air Separator Temperature Indicator

## ELECTRICAL CONTROL PANEL

### Description

The electrical controls shall be contained within a National Electrical Manufacturers' Association Type One enclosure, and all visual indicators and manual controls shall be flush mounted on the face of the enclosure cover. The electrical controls shall consist of the following: power distribution circuit breakers, an indoor switchgear unit complete with an alternating current voltmeter, ammeter, current transformer, and all controls necessary for alternating-current generator operation.

## INSULATION

### Description

The fiberglass insulation for the air separator shall be Owens-Corning Fiberglass Corporation Basic Fiber No. 28, Type E.

## SECTION V

### GENERATOR MASTER VALVE AND TEMPERATURE INDEX

For identification and reference purposes, the Generator valves and temperature indicators shall be assigned letter-and-number symbols. Insofar as possible, the letter in each valve symbol shall be the initial of the fluid normally controlled by the valve. The letters in each temperature indicator symbol shall denote the type of instrument used to determine the temperature. Temperature indicators shall be either dial thermometers, or millivolt-type, direct-reading pyrometers. This system of identification has been applied in the flow diagram of Figures 1, 2, 3 and 4.

#### Symbols

#### Names of Valves

##### AIR VALVES

A1-A	Air Expansion to Oxygen Column
A1-B	Air Expansion to Nitrogen Column
A7	Expansion-Engine Air Inlet
A10	First-Stage Condensate-Trap Blow-Off
A11	Second-Stage Condensate-Trap Blow-Off
A12	Third-Stage Condensate-Trap Blow-Off
A16	Heat Exchanger Blow-Off
A20	First-Stage Pressure-Gage Shut-Off
A21	Second-Stage Pressure-Gage Shut-Off
A22	Third-Stage Pressure-Gage Shut-Off
A26	Air Flow Control
A30	Main-Air Shut-Off
A54	High-Pressure Blow-Down
A81	Moisture Accumulator Tank Drain
A84	Expansion-Engine Inlet Blow-Off
A86-A	Dry-Supply-Air Shut-Off
A86-B	Wet-Supply-Air Shut-Off
A104	High-Pressure-Air Exchanger Bypass
A105	Defrost-Air Exchanger Bypass
A106	Defrost-Air Exchanger Bypass Shut-Off
A107	High-Pressure-Air Leak Vent
A110	Expander Bypass
A111	Aftercooler Bypass
A128	Supply-Air Pressure Regulator
A129	Supply-Air Reservoir Drain
A130	Expander Discharge Column Feed

##### OXYGEN VALVES

O1	Crude Oxygen Expansion
O7	Oxygen-Pump Feed Control
O10	Pure-Oxygen Test
O14-A	Low-Pressure-Oxygen-Column Defrost
O14-B	Low-Pressure-Nitrogen-Column Defrost
O20	Low-Pressure-Column Gage Shut-Off

021	High-Pressure-Oxygen-Gage Shut-Off
022	Pure-Oxygen Lower Liquid-Level-Gage Shut-Off
023	Pure-Oxygen Upper Liquid-Level-Gage Shut-Off
024	Pure-Oxygen Upper Liquid-Level-Gage Vent
025	Pure-Oxygen Lower Liquid-Level-Gage Vent
026	Crude-Oxygen Upper Liquid-Level-Gage Shut-Off
027	Crude-Oxygen Lower Liquid-Level-Gage Shut-Off
028	Crude-Oxygen Upper Liquid-Level-Gage Vent
029	Crude-Oxygen Lower Liquid-Level-Gage Vent
038	Oxygen-Liquid-Level-Gage Vent
039	Oxygen-Liquid-Level-Gage Vent
040	Oxygen-Liquid-Level-Gage Equalizer
050	Column-Pressure-Gage Shut-Off
084	Crude-Oxygen Upper Liquid-Level-Gage Vent
085	Crude-Oxygen Lower Liquid-Level-Gage Vent
087	Pure Liquid Offtake
094	Pure-Oxygen Liquid-Level-Gage Equalizer
095	Crude-Oxygen Liquid-Level-Gage Equalizer
0101	Hydrocarbon-Adsorber Inlet
0102	Hydrocarbon-Adsorber Outlet
0103	Hydrocarbon-Adsorber Bypass
0108-A	Oxygen-Column Crude-Oxygen Feed Shut-Off
0108-B	Nitrogen-Column Crude-Nitrogen Feed Shut-Off
0118	Pure Gas Offtake
0131	Pure-Oxygen Subcooler Inlet

#### NITROGEN VALVES

N1-A	Oxygen-Column Crude Oxygen Expansion Valve
N1-B	Nitrogen-Column Crude-Nitrogen Expansion Valve
N12	Noncondensable-Gas Blow-Off
N13	Exchanger Defrost Outlet
N14-A	High-Pressure-Oxygen-Column Defrost
N14-B	High-Pressure-Nitrogen-Column Defrost
N15	Air-Separator-Jacket Nitrogen Feed
N20	High-Pressure-Column Gage Shut-Off
N30	Noncondensable-Gas Shut-Off
N37	Pump-Nitrogen Feed Control
N56	Oxygen-Pump Defrost Inlet
N83	High-Pressure-Nitrogen-Gage Shut-Off
N104	Hydrocarbon-Adsorber Defrost Inlet
N105	Hydrocarbon-Adsorber Defrost Outlet
N106	Expander Defrost Inlet
N108	Crude-Nitrogen Upper Liquid-Level-Gage Shut-Off
N109	Crude-Nitrogen Lower Liquid-Level-Gage Shut-Off
N110	Crude-Nitrogen Upper Liquid-Level-Gage Vent
N111	Crude-Nitrogen Lower Liquid-Level-Gage Vent
N112	Crude-Nitrogen Liquid-Level-Gage Equalizer
N117	Nitrogen-Column Noncondensable-Gas Shut-Off
N127	High Purity Nitrogen Test
N137	Pure-Nitrogen Subcooler Inlet
N142	Pure-Nitrogen Column Pressure Gage Shut-Off
N144	Nitrogen Pump Defrost Inlet
N151	Nitrogen Condenser Upper Liquid-Level-Gage Inlet

N152	Nitrogen Condenser Lower Liquid-Level-Gage Inlet
N153	Nitrogen Condenser Upper Liquid-Level-Gage Vent
N154	Nitrogen Condenser Lower Liquid-Level-Gage Vent
N155	Nitrogen Condenser Liquid-Level-Gage Equalizer

### Symbols

### Temperatures Indicated

### THERMOMETER TEMPERATURES

TH1	Air Leaving First-Stage-Intercooler of Air-Compressor
TH2	Air Leaving Second-Stage-Intercooler of Air-Compressor
TH3	Air Leaving Third-Stage-Aftercooler of Air-Compressor
TH4	Air Leaving Oxygen-Vaporizer
TH5	Gaseous Product Leaving Vaporizer

### OPERATOR MASTER VALVE AND TEMPERATURE INDEX

### Symbols

### Temperatures Indicated

### TEMPERATURE INDICATION TEMPERATURES

T1	Air Entering (Air Leaving) Warm-Heat-Exchanger
T2	Air Leaving (Air Entering) Warm-Heat-Exchanger
T3	Air Leaving (Air Entering) Cold-Heat-Exchanger
T4	Air Entering (Air Leaving) Cold-Heat-Exchanger
T5	Nitrogen-Rich-Air Entering Turbine-Compressor
T6	Nitrogen-Rich-Air Leaving Turbine-Compressor
T7	Nitrogen-Rich-Air Entering Air-Liquidifier
T8	Pure-Liquid-Oxygen Entering Liquid-Oxygen-Subcooler
T9	Pure-Liquid-Oxygen Leaving Liquid-Oxygen-Subcooler
T10	Defrosted Air Leaving Air-Liquidifier
T11	Reboiling-Air Leaving Hydrocarbon-Subcooler